

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

*Various Routes*  
OVD SIN STR REP & REPL 2008-9  
*Various Counties*  
Sheet 50 of 105  
Contract Number 44973

District 3  
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	3-01	State I.D. No.:	3C053I055R192.8		
County:	Livingston	Route:	I-55	M.P.:	192.8
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	48.00			
REMOVE & REINSTALL WALKWAY	FOOT	16.50			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
OVERHEAD SIGN STRUCTURE CANTILEVER, TYPE II-C-A	FOOT	30.00			
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	7.10			
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
FURNISH & INSTALL WALKWAY TIE DOWN BOLT	EACH	2.00			
This sign structure is being completely replaced.					

Location No.:	3-02	State I.D. No.:	3C053I055L194.4		
County:	Livingston	Route:	I-55	M.P.:	194.4
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	49.00			
REMOVE & REINSTALL WALKWAY	FOOT	16.50			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
OVERHEAD SIGN STRUCTURE CANTILEVER, TYPE II-C-A	FOOT	30.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	EACH	7.10			
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00			
FURNISH & INSTALL WALKWAY TIE DOWN BOLT	EACH	4.00			
This sign structure is being completely replaced.					

Location No.:	3-03	State I.D. No.:	3S050I080L078.9		
County:	LaSalle	Route:	I-80	M.P.:	78.9
				Direction:	WB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A	FOOT	96.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	498.00			
REMOVE & REINSTALL WALKWAY	FOOT	56.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00			
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6.00			
REPLACE / TIGHTEN CLIP PER SIGN	EACH	3.00			
This sign structure is being down sized from a Type IV truss to a Type II truss. The existing end support will be reused.					