

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	114 BY-R-1	WILL	139	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN: 80% FEDERAL, 20% STATE CONSTRUCTION TYPE CODE		
				IDOT		
				ROAD J000-2A	BRIDGE X081-2A	J000-2A
* Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	2,779	2,779		
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
* Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2			2
* Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	3			3
* Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY-REDIRECTIVE), TEST LEVEL 2	EACH	2			2
* Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4			4
◇ * Z0065000	SETTINGS PILES IN ROCK	EACH	40		40	
* Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	6		6	
⊙ * Z0076600	TRAINEES	HOURL	1500	1500		
* XX002134	CONCRETE CURB AND GUTTER OUTLET SPECIAL	EACH	2	2		
* XX005656	INLET FILTER CLEANING	EACH	42	42		
◇ * XX005733	POLYUREA PAVEMENT MARKING - LINE 12"	FOOT	290	290		
◇ * XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	1,468	1,468		
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4		
* X0323830	DRAINAGE SCUPPERS DS-11	EACH	10		10	
* X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1,385	1,385		
* X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1,385	1,385		
* X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	6,210	5,140	1,070	
⚠ * X0325318	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU YD	1,000	1,000		
* X0712400	TEMPORARY PAVEMENT	SQ YD	6,066	6,066		
* X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2		
* X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1		
* X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	2		
* X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1	
* X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1	
* X0325858	ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48"	FOOT	2,880		2,880	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	66		66	
X0325834	HORIZONTAL STRIP DRAINS	FOOT	8400	8400		
X0325833	WICK DRAINS	FOOT	30,736	30,736		

- ⊙ 4080
- * DENOTES NON-STANDARD PAY ITEM REFER TO SPECIAL PROVISIONS
- ◇ SPECIALITY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE AUGUST 17, 2007
DRAWN BY RTA
CHECKED BY JCM