

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	114 BY-R-1	WILL	139	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

EARTHWORK QUANTITIES

LOCATION STATION TO STATION	EARTH EXCAVATION (SUITABLE) (CU YD)						REMOVAL & DISPOSAL OF UNSUITABLE MAT'L (CU YD)					EXCAVATION TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE, 15%) (CU YD)					EMBANKMENT (CU YD)					LOCATION STATION TO STATION				
	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2		STAGE 3	STAGE 4	STAGE 5	
3195+17 3196+00	26	0	0	0	0	12	0	0	0	0	0	0	22	0	0	0	0	10	5	0	0	0	0	6	3195+00 3196+00	
3196+00 3197+00	45	0	0	0	0	14	0	0	0	0	0	0	38	0	0	0	0	12	8	0	0	0	0	16	3196+00 3197+00	
3197+00 3198+00	59	0	0	0	0	18	0	0	0	0	0	0	50	0	0	0	0	15	11	0	0	0	0	28	3197+00 3198+00	
3198+00 3199+00	82	44	0	0	0	25	0	0	0	0	0	0	70	38	0	0	0	21	18	10	0	0	0	36	3198+00 3199+00	
3199+00 3200+05	47	80	0	0	0	29	0	62	0	0	0	0	40	68	0	0	0	25	11	34	0	0	0	40	3199+00 3200+05	
3200+05 3201+00	0	77	0	0	0	26	0	123	0	0	0	0	0	65	0	0	0	22	0	23	0	0	0	36	3200+05 3201+00	
3201+00 3202+00	0	86	0	0	0	21	0	110	0	0	0	0	0	73	0	0	0	18	0	1	0	0	0	38	3201+00 3202+00	
3202+00 3203+00	0	157	14	28	7	9	0	0	0	0	0	0	0	134	12	24	6	7	0	0	0	0	25	19	3202+00 3203+00	
3203+00 3204+00	0	312	27	126	16	0	0	0	0	0	0	0	0	265	23	107	14	0	0	6	6	0	38	0	3203+00 3204+00	
3204+00 3205+00	0	399	22	158	20	0	0	0	0	0	0	0	0	339	19	134	17	0	0	22	26	14	25	0	3204+00 3205+00	
3205+00 3206+00	0	416	21	152	19	0	0	77	0	42	0	0	0	354	18	129	16	0	0	46	49	88	25	0	3205+00 3206+00	
3206+00 3207+00	0	247	28	118	19	0	0	150	0	88	0	0	0	210	24	101	16	0	0	61	60	151	27	0	3206+00 3207+00	
3207+00 3208+00	0	58	23	36	30	0	0	115	0	158	0	0	0	49	19	31	26	0	0	349	54	941	21	0	3207+00 3208+00	
3208+00 3208+60	0	12	4	6	12	0	0	128	0	141	0	0	0	10	3	5	10	0	0	602	47	1096	10	0	3208+00 3208+60	
BRIDGE OVER DUPAGE RIVER																										
3211+36 3212+00	107	0	0	1	11	0	0	0	0	0	0	0	91	0	0	1	9	0	589	1077	0	535	18	0	3211+36 3212+00	
3212+00 3213+00	114	0	0	1	17	0	0	0	0	0	0	0	97	0	0	1	14	0	903	1437	0	800	28	0	3212+00 3213+00	
3213+00 3214+00	46	0	0	1	8	7	0	0	0	0	0	0	39	0	0	1	7	6	768	1245	0	616	14	8	3213+00 3214+00	
3214+00 3215+00	94	0	0	2	0	15	0	0	0	0	0	0	80	0	0	2	0	13	436	1050	0	337	0	18	3214+00 3215+00	
3215+00 3216+00	295	37	0	14	0	26	0	0	0	0	0	0	251	32	0	12	0	22	150	480	0	126	0	22	3215+00 3216+00	
3216+00 3217+00	361	106	0	48	0	36	0	0	0	0	0	0	307	90	0	41	0	30	62	99	0	31	0	24	3216+00 3217+00	
3217+00 3218+00	203	88	0	96	0	33	0	0	0	0	0	0	172	74	0	82	0	28	111	60	0	21	0	25	3217+00 3218+00	
3218+00 3219+00	95	35	0	92	0	32	0	0	0	0	0	0	81	30	0	78	0	27	162	91	0	26	0	25	3218+00 3219+00	
3219+00 3220+00	65	31	0	49	0	30	0	0	0	0	0	0	56	27	0	41	0	26	122	99	0	25	0	25	3219+00 3220+00	
3220+00 3221+00	42	33	0	28	0	28	0	0	0	0	0	0	35	28	0	24	0	24	75	86	0	21	0	25	3220+00 3221+00	
3221+00 3222+00	44	18	0	27	0	31	0	0	0	0	0	0	38	15	0	23	0	26	119	37	0	21	0	25	3221+00 3222+00	
3222+00 3223+00	64	0	0	28	0	31	0	0	0	0	0	0	54	0	0	24	0	26	171	0	0	22	0	22	3222+00 3223+00	
3223+00 3224+00	49	0	0	22	0	23	0	0	0	0	0	0	42	0	0	19	0	20	115	0	0	14	0	13	3223+00 3224+00	
3224+00 3225+00	26	0	0	16	0	15	0	0	0	0	0	0	22	0	0	14	0	13	39	0	0	7	0	6	3224+00 3225+00	

SUB-TOTAL	1864	2235	139	1050	159	461	0	764	0	429	0	0	1585	1900	118	893	135	392	3874	6914	242	4891	231	459	SUB-TOTAL
TOTAL	5,907						1,193						5,021						16,610						TOTAL

REVISIONS	
NAME	DATE
ADDENDUM A	10-26-07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
DISTRICT NO. 1 SCHAUMBURG

SCHEDULE OF QUANTITIES

SCALE NONE  
DATE AUGUST 17, 2007

DRAWN BY RTA  
CHECKED BY JCM