CONTRACT NO. 60C19

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
338	114 BY-R-1	WILL	139	11
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FAP 338 (IL RTE. 59)		

EARTHWORK QUANTITIES

LOCATION STATION TO STATION		POROUS GRANULAR EMBANKMENT SUBGRADE (CU YD)						LIGHTWEIGHT CELLULAR CONCRETE FILL (CU YD)						EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)						TOPSOIL EXCAVATION & PLACEMENT (CU YD)						* TOPSOIL FURNISHED & PLACED, 4" (CU YD)						LOCATION STATION TO STATION	
		PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	PRE-STAGE	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5		
3195+00	3196+00	0	0	0	0	0	0	0	0	0	0	0	0	17	0	0	0	0	4	18	0	0	0	0	0	10	0	0	0	0	4	3195+00	3196+00
3196+00	3197+00	0	0	0	0	0	0	0	0	0	0	0	0	30	0	0	0	0	-4	32	0	0	0	0	0	12	0	0	0	0	9	3196+00	3197+00
3197+00	3198+00	0	0	0	0	0	0	0	0	0	0	0	0	39	0	0	0	0	-13	45	0	0	0	0	0	11	0	0	0	0	20	3197+00	3198+00
3198+00	3199+00	0	0	0	0	0	0	0	0	0	0	0	0	52	28	0	0	0	-15	64	35	0	0	0	0	12	6	0	0	0	32	3198+00	3199+00
3199+00	3200+05	0	85	0	0	0	0	0	0	0	0	0	0	29	34	0	0	0	-15	37	75	0	0	0	0	6	11	0	0	0	39	3199+00	3200+05
3200+05	3201+00	0	152	0	0	0	0	0	0	0	0	0	0	0	42	0	0	0	-14	0	65	0	0	0	0	0	10	0	0	0	34	3200+05	3201+00
3201+00	3202+00	0	90	0	0	0	0	0	0	0	0	0	0	0	72	0	0	0	-20	0	58	0	0	0	0	0	10	0	0	0	29	3201+00	3202+00
3202+00	3203+00	0	0	0	0	0	0	0	0	0	0	0	0	0	133	12	24	-19	-11	0	54	0	0	0	0	0	11	0	2	12	13	3202+00	3203+00
3203+00	3204+00	0	0	0	0	0	0	0	0	0	0	0	0	0	259	17	107	-25	0	0	63	0	24	0	0	0	16	0	17	22	0	3203+00	3204+00
3204+00	3205+00	0	0	0	0	0	0	0	0	0	0	0	0	0	317	-7	120	-8	0	0	59	0	47	0	0	0	21	0	24	23	0	3204+00	3205+00
3205+00	3206+00	0	51	0	47	0	0	0	0	0	0	0	0	0	308	-31	41	-9	0	0	64	0	51	0	0	0	24	0	20	25	0	3205+00	3206+00
3206+00	3207+00	0	135	0	110	0	0	0	0	0	0	0	0	0	149	-36	-50	-11	0	0	72	0	56	0	0	0	17	0	34	24	0	3206+00	3207+00
3207+00	3208+00	0	90	0	152	0	0	0	0	0	0	0	0	0	-300	-35	-911	4	0	0	77	0	79	0	0	0	8	0	55	26	0	3207+00	3208+00
3208+00	3208+60	0	0	0	0	0	0	0	387	0	576	0	0	0	-591	-44	-1091	0	0	0	27	0	31	0	0	0	2	0	19	8	0	3208+00	3208+60
														BRIDGE OVER DUPAGE RIVER																			
3211+36	3212+00	0	0	0	0	0	0	0	0	0	0	0	0	-498	-1077	0	-534	-9	0	97	64	0	0	0	0	30	21	0	38	3	0	3211+36	3212+00
3212+00	3213+00	0	0	0	0	0	0	0	0	0	0	0	0	-806	-1437	0	-799	-14	0	145	92	0	0	0	0	45	29	0	59	3	0	3212+00	3213+00
3213+00	3214+00	0	0	0	0	0	0	0	0	0	0	0	0	-729	-1245	0	-615	-7	-2	124	98	0	0	0	0	37	30	0	41	1	3	3213+00	3214+00
3214+00	3215+00	0	0	0	0	0	0	0	0	0	0	0	0	-356	-1050	0	-335	0	-6	110	103	0	0	0	0	33	32	0	23	0	6	3214+00	3215+00
3215+00	3216+00	0	0	0	0	0	0	0	0	0	0	0	0	101	-449	0	-114	0	0	110	84	0	0	0	0	35	19	0	27	0	20	3215+00	3216+00
3216+00	3217+00	0	0	0	0	0	0	0	0	0	0	0	0	245	-9	0	10	0	6	110	70	0	0	0	0	33	11	0	34	0	32	3216+00	3217+00
3217+00	3218+00	0	0	0	0	0	0	0	0	0	0	0	0	61	14	0	61	0	3	105	58	0	0	0	0	28	9	0	46	0	29	3217+00	3218+00
3218+00	3219+00	0	0	0	0	0	0	0	0	0	0	0	0	-81	-61	0	53	0	2	87	47	0	0	0	0	17	5	0	47	0	27	3218+00	3219+00
3219+00	3220+00	0	0	0	0	0	0	0	0	0	0	0	0	-67	-73	0	16	0	1	65	39	0	0	0	0	9	2	0	35	0	26	3219+00	3220+00
3220+00	3221+00	0	0	0	0	0	0	0	0	0	0	0	0	-39	-58	0	3	0	-1	50	32	0	0	0	0	8	0	0	24	0	24	3220+00	3221+00
3221+00	3222+00	0	0	0	0	0	0	0	0	0	0	0	0	-81	-22	0	2	0	1	63	15	0	0	0	0	7	0	0	22	0	23	3221+00	3222+00
3222+00	3223+00	0	0	0	0	0	0	0	0	0	0	0	0	-116	0	0	2	0	5	78	0	0	0	0	0	7	0	0	24	0	22	3222+00	3223+00
3223+00	3224+00	0	0	0	0	0	0	0	0	0	0	0	0	-74	0	0	5	0	6	55	0	0	0	0	0	4	0	0	16	0	16	3223+00	3224+00
3224+00	3225+00	0	0	0	0	0	0	0	0	0	0	0	0	-17	0	0	7	0	6	18	0	0	0	0	0	0	0	0	7	0	6	3224+00	3225+00
~~BACKFILL FOR STORM SEWER~~											46																						
SUB-TOTAL		0	601	0	309	0	0	0	387	0	622	0	0	-2289	-5014	-124	-3998	-96	-67	1412	1348	0	287	0	0	342	294	0	611	145	412	SUB-TOTAL	
TOTAL		910						1,009						-11,589						3,047						1,804						TOTAL	

NOTES:

* TOPSOIL FURNISH & PLACE, 4" IS USED FOR TABULATION PURPOSES, TO DETERMINE TOPSOIL BALANCE AND IS NOT REQUIRED ON THE PROJECT.

REVISIONS	
NAME	DATE
1 ADDENDUM A	10-26-07

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SCHEDULE OF QUANTITIES

SCALE NONE
DATE AUGUST 17, 2007
DRAWN BY RTA
CHECKED BY JCM