

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN						
				100% STATE SFTY-2A						
50102400	CONCRETE REMOVAL	CU YD	8.2	8.2						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	5	5						
50300260	BRIDGE DECK GROOVING	SQ YD	70.4	70.4						
50300300	PROTECTIVE COAT	SQ YD	112.3	112.3						
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	549.2	549.2						
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	500	500						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,450	2,450						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2						
67100100	MOBILIZATION	L SUM	1	1						
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1						
70101000	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	150	150						
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	150	150						
X0301424	SILICONE JOINT SEALER	FOOT	37	37						
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	553.1	553.1						
X0321781	MECHANICAL SPLICE	EACH	135	135						
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48						
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	77.6	77.6						
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1						

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev. 10-26-07

PLOT DATE: 9/5/2007

Rev.

9/5/2007  
c:\brco\brco\3597\3597\07101\07101-1\06.dgn