F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
374	G-B-I-1	COOK	15	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60D59

Beam 10

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk.N.Abt.	12994.866	41.463	644.635	644.635
North Bearing	12996.134	41.478	644.641	644.641
A	13006.204	41.585	644.685	644.709
B	13016.273	41.675	644.719	644.754
C	13026.343	41.749	644.742	644.772
D	13036.413	41.805	644.756	644.768
Pier 1	13046.483	41.845	644.761	644.761
E	13056.553	41.869	644.755	644.765
F	13066.615	41.875	644.739	644.765
G	13076.615	41.875	644.715	644.747
H	13086.615	41.875	644.680	644.706
I	13096.615	41.875	644.637	644.647
Pier 2	13106.615	41.875	644.584	644.584
J	13116.615	41.875	644.522	644.534
K	13126.615	41.875	644.451	644.481
L	13136.615	41.875	644.370	644.406
M	13146.615	41.875	644.284	644.308
South Bearing	13156.615	41.875	644.198	644.198
Bk.S.Abt.	13157.875	41.875	644.188	644.188

Right Edge of Deck

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk.N.Abt.	12994.412	44.416	644.713	644.713
North Bearing	12995.681	44.431	644.719	644.719
A	13005.755	44.539	644.763	644.787
B	13015.830	44.630	644.797	644.833
C	13025.905	44.704	644.821	644.851
D	13035.979	44.761	644.836	644.848
Pier 1	13046.055	44.802	644.840	644.840
E	13056.130	44.826	644.835	644.845
F	13066.199	44.833	644.820	644.846
G	13076.199	44.833	644.795	644.828
H	13086.199	44.833	644.762	644.787
I	13096.199	44.833	644.719	644.729
Pier 2	13106.199	44.833	644.666	644.666
J	13116.199	44.833	644.605	644.616
K	13126.199	44.833	644.534	644.564
L	13136.199	44.833	644.454	644.489
M	13146.199	44.833	644.368	644.391
South Bearing	13156.199	44.833	644.282	644.282
Bk.S.Abt.	13157.459	44.833	644.271	644.271

FOR INFORMATION ONLY

Notes:
See Sheet 6 for Screed Plan.

All Offsets Taken from Centerline of Roadway.

STV Incorporated
Engineers/Architects/Planners/Construction Managers
200 W. Monroe Street, Suite 1650
Chicago, IL 60606-5013
312/553-0655, FAX 312/553-0661

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 21
MILWAUKEE AVE. OVER DES PLAINES RIVER
F.A.P. ROUTE 374 SECTION G-B-I-1
COOK COUNTY, SN 016-6566

DECK ELEVATIONS

DESIGN BY: BTO DRAWN BY: BTO
DATE: 8/29/07 CHECKED BY: JAN CHECKED BY: JAN

...\Sheet Files\3568_374B_D65.dgn 8/29/2007 11:26:28 AM