

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
846	4B-1-R	WILL	87	5
STA. 1301+00		TO STA. 1309+00		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				


CONTRACT No. 62269

**LEGEND**

- ① EXISTING GROUND
- ② EXISTING BITUMINOUS PAVEMENT ± 3"
- ③ EXISTING BITUMINOUS BASE COURSE, ± 10"
- ④ EXISTING SUBBASE GRANULAR MATERIALS, ± 4"
- ⑤ PAVED SHOULDER, ± 8"
- ⑥ EXISTING STEEL BEAM GUARDRAIL TO BE REMOVED (SB FROM STA. 1305+53.020 TO STA. 1307+03.316) (NB FROM STA. 1302+69.241 TO STA. 1304+46.988)
- ⑦ EXISTING AGGREGATE SHOULDER TO BE REMOVED, ± 6"
- ⑧ HMA SURFACE TO BE REMOVED, ¾"
- ⑨ HMA SURFACE TO BE REMOVED, 2¼"
- ⑩ PROPOSED STRIP REFLECTIVE CRACK CONTROL TREATMENT
- ⑪ PROPOSED LEVELING BINDER (MACHINE METHOD), N50, ¾"
- ⑫ PROPOSED HOT-MIX ASPHALT BINDER COURSE, IL-19, N50, VARIES (2¼" MIN)
- ⑬ PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50, 1½"
- ⑭ PROPOSED HOT-MIX ASPHALT BASE COURSE, 10"
- ⑮ PROPOSED DISTRICT'S AGGREGATE SUBGRADE, 12"
- ⑯ PROPOSED SUBBASE GRANULAR MATERIAL, TYPE B, 6"
- ⑰ PROPOSED HOT-MIX ASPHALT SHOULDER, 6"
- ⑱ PROPOSED AGGREGATE WEDGE SHOULDER, TYPE B
- ⑲ PROPOSED STEEL BEAM GUARDRAIL, TYPE A (SB FROM STA 1305+54.73 TO STA 1308+50.98) (NB FROM STA 1301+48.88 TO STA 1304+45.13)
- ⑳ COMPOSITE FURNISH AND PLACE, 4", SEEDING, CLASS 4
- ㉑ PROPOSED FILL (FURNISHED EXCAVATION)
- ㉒ PROPOSED BENCHING.
- ㉓ PIPE UNDERDRAINS

**NOTES**

- 1. FOR SOUTHBOUND AND NORTHBOUND BRIDGE CROSS SECTIONS SEE SHT#---
- 2. FOR BRIDGE APPROACH PAVEMENT SEE STANDARD 420401
- 3. THE \* MARK INDICATES ADDITIONAL SHOULDER (BITUMINOUS STABILIZATION FOR THE STEEL PLATE BEAM GUARDRAIL) (SB FROM STA 1305+54.73 TO STA 1308+50.98) (NB FROM STA 1301+48.88 TO STA 1304+45.13)

 ITEM TO BE REMOVED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
IL RTE 53 OVER PRAIRIE CREEK  
TYPICAL SECTIONS

SCALE: NOT TO SCALE  
DATE: AUGUST 2007  
DRAWN BY: JLA/RM/FZ  
CHECKED BY: MK/SMK

