** (7-YV-1&8R-1) WRS&7-YV-1-BR

F.A.P. RTE.	SECTION		COUNTY	TOTAL	SHEET NO.
345	**		COOK	22	2
STA.		TO:	STA.		
FFD. ROA	D DIST, NO. 1	II I INOTS	FED. AT	D PROJECT	

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED) THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

ALL DAMAGE TO EXISTING PAVEMENT MARKING, RAISED REFLECTIVE PAVEMENT MARKINGS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT). IN ACCORDANCE WITH "BUTT JOINT AND HOT-MIX ASPHALT TAPER DETAILS" SHEET INCLUDE IN THE PLANS, UNLESS OTHERWISE SPECIFIED.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREA.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESES LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURRING THE CONSTRUCTION OF THIS PROJECT.

DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN THE PLANS.

THE ENGINEER SHALL CONTACT DON CHIARUGI TRAFFIC FIELD ENGINEER AT (847) 741-5302. A MINIMUM OF (2) WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

CONCRETE WEARING SURFACE SHALL HAVE A SEVEN DAY MINIMUM CURE.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS

	-		
REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	TO ANCIDETATION
NAME	DATE	TELINOIS DEFARTMENT OF TRANSFORTATION	
		INDEX OF LIST OF STATE GENERAL	STANDARDS
		SCALE: VERT. : NONE DATE	DRAWN BY: CHECKED BY:

INDEX OF SHEETS

8/30/2007 c:#projects#d!13703#design_stage.dgn VI#BD7

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	EXIST. AND PROP. TYPICAL SECTION
4A	EXIST. STD 1909 (FOR INFORMATION ONLY)
5	EXIST. AND PROP. APPROACH PAVEMENT PLAN
6-7	SUGGESTED STAGES OF CONSTRUCTION & TRAFFIC CONTROL
8-17	BRIDGE PLANS (SN: 016-0219)
18	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAY
19	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANCE)
20	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
21	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
22	ARTERIAL ROAD INFORMATION SIGN

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
420401 <i>-05</i>	BRIDGE APPROACH PAVEMENT
606001-03	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
631026 -03	TRAFFIC BARRIER TERMINAL, TYPE 5
701426 - 02	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS \geq 45 MPH
701601- 04	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
702001-06	TEMPORARY CONTROL DEVICE
704001-03	TEMPORARY CONCRETE BARRIER