F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
852	18 B-5-R-2	WILL	66	4
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT # 62845

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY I000-2A	BRIDGE SN 099-4643 X081-2A				
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	4					
	54215547	METAL END SECTIONS 12"	EACH	2	2					
	542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	262	262					
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	72		72				
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	8	8					
	60100945	PIPE DRAINS 12"	FOOT	60	60					
	60107600	PIPE UNDERDRAINS 4"	FOOT	232	232					
	60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	148		148				
	60600605	CONCRETE CURB, TYPE B	FOOT	120	120					
	60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2	2					
	60900515	CONCRETE THRUST BLOCKS	EACH	2	2					
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	675	675					
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4					
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3					
*	63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	1					
	63200310	GUARDRAIL REMOVAL	FOOT	737	737					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12					
	67100100	MOBILIZATION	L SUM	1	1					
	~~70100450~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701201~~	~~L SUM~~	~~1~~	~~1~~					
	~~70100460~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701306~~	~~L SUM~~	~~1~~	~~1~~					
	~~70100500~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701326~~	~~L SUM~~	~~1~~	~~1~~					
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70					
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	594	594					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3727	3727					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	15	15					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY FED. 90% STATE 10% I000-2A	BRIDGE SN 099-4643 FED. 90% STATE 10% X081-2A				
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	7537	7537					
	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	62	62					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	66	66					
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1210	1210					
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1210	1210					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3727	3727					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	15	15					
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	546	546					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16					
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3					
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	16	16					
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10					
	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1					
	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1					
*	81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1850	1850					
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100	100					
*	83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	9	9					
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	9	9					
*	87000172	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4 AND NO. 6 GROUND	FOOT	150	150					
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77.1	77.1					
	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6					
	X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	2	2					
	X0712400	TEMPORARY PAVEMENT	SQ YD	648	648					
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1				
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1				

* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

U.S. RTE. 52 OVER PRAIRIE CREEK

PLOT DATE: 8/28/2007

8/28/2007
pw:\\pwdevusr\ildot149801\Estimation.m32