

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2079	CARROLL & OGLE		232	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	80% FED. 20% STATE TOTAL QUANTITY	1000-1A COUNTY		SFTY-2A	Y030-1E	Y031-1F (US 52)	
				CARROLL	OGLE	COUNTY	COUNTY	CARROLL	OGLE
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	9,056	1,467	7,589				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2,066	417	1,649				
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	286	36	250				
44000100	PAVEMENT REMOVAL	SQ YD	7,270	5,497	1,773				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	79,802	0	79,802				
44002600	GUTTER OUTLET REMOVAL	FOOT	34	34					
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	521	410	111				
44201421	CLASS C PATCHES, TYPE IV, 15 INCH	SQ YD	639		639				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	37,675	3,510	34,165				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,499	805	694				
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	309	210	99				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1					
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1				
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1				
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1					
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1					
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1	1					
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1		1				
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1		1				
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	EACH	1		1				
50101200	REMOVAL OF EXISTING STRUCTURES NO. 10	EACH	1		1				
50101300	REMOVAL OF EXISTING STRUCTURES NO. 11	EACH	1		1				
50101400	REMOVAL OF EXISTING STRUCTURES NO. 12	EACH	1		1				
50101410	REMOVAL OF EXISTING STRUCTURES NO. 13	EACH	1		1				
50102400	CONCRETE REMOVAL	CU YD	7.7		7.7				
50102600	CONCRETE REMOVAL	EACH	4	4					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4.6		4.6				
50300300	PROTECTIVE COAT	SQ YD	122		122				
50300530	FLOOR DRAIN EXTENSION	EACH	2		2				
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	777		777				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	116		116				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,130		2,130				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAS ROUTE 2079 (US 52)
SECTION (16,17,18)RS-3 & (16BR)M-1
CARROLL & OGLE COUNTIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____

PLOT DATE = Fri, Nov 09, 08:54:09, 2007
 FILE NAME = C:\Users\j2026265\Documents\64237\64237.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = j2026265