

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2079		CARROLL & OGLE	232	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CODE NUMBER	PAY ITEMS	UNIT	80% FED. 20% STATE TOTAL QUANTITY	1000-1A COUNTY		SFTY-2A COUNTY	YO30-1E COUNTY	YO31-1F (US 52) COUNTY	
				CARROLL	OGLE	OGLE	CARROLL	CARROLL	OGLE
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	38		38				
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	219		219				
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	58		58				
542A5515	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 60"	FOOT	42		42				
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	303	108	195				
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	252	154	98				
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	160	74	86				
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	57	57					
542D5479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	46		46				
54207579	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 24"	FOOT	40		40				
54213450	END SECTIONS 15"	EACH	12	4	8				
54213459	END SECTIONS 24"	EACH	10	6	4				
54213471	END SECTIONS 36"	EACH	1	1					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2		2				
54214299	END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2		2				
54214929	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 24"	EACH	2		2				
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	2	2					
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	1		1				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	52	52					
58700300	CONCRETE SEALER	SQ FT	15		15				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	16.0	8.2	7.8				
63200310	GUARDRAIL REMOVAL	FOOT	550		550				
63500105	DELINEATORS	EACH	43	17	26				
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	116	46	70				
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	7	1	6				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	13	1	12				
67100100	MOBILIZATION	L SUM	1	0.5	0.5				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5				

* SPECIALTY ITEM

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION FAS ROUTE 2079 (US 52) SECTION (16,17,18)RS-3 & (16BR)M-1 CARROLL & OGLE COUNTIES DRAWN BY CHECKED BY
-----------	---

SUMMARY OF QUANTITIES

PLOT DATE = Fri Mar 05 06:34:43 2007
 FILE NAME = G:\projects\16282685\62685.dgn
 PLOT SCALE = 1"=50'
 USER NAME = dssad