

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2079	**	CARROLL&OGLE	232	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*(US 52)		**(16,17,18)RS-3 & (16BR)M-1		

# SCHEDULE OF QUANTITIES

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION			
	Carroll County			
	Existing IL RTE 64			
1818.5	Sta 1508+78.5	-	Sta	1511+43.77
	Existing Brookville Road			
2975.7	Sta 117+75	-	US RTE 52 EOP	
	Existing Ogle Road			
703.3	Sta 158+05	-	Sta	1513+15
5497	Sub-total - Carrdl County			
	Ogle County			
	Existing IL RTE 64			
1152.9	Sta 0+00	-	Sta	4+00
	Existing Ogle Road			
620.3	Sta 158+05	-	Sta	0+00
1773	Sub-total - Ogle County			
7270	Grand Total (Carrdl and Ogle Counties)			

44002600 GUTTER OUTLET REMOVAL

FOOT	LOCATION	REMARKS
	Carroll County	
	US RTE 52	
34	LT Sta 1509+20	- Sta 1509+54 SE Quadrant
34	Grand Total (Carrdl County)	

44201359 CLASS C PATCHES, TYPE IV, 10 INCH

SQ YD	LOCATION	REMARKS
	Carroll County	
	US RTE 52/IL RTE 64	
350.0	Sta 1506+80	- Sta 1508+20 Removal of Ex. Pipe Culverts
	US RTE 52	
60.0	Sta 1509+88	- Sta 1510+12 15" Storm Sewer Crossing
410	Sub-total - Carrdl County	
	Ogle County	
	US RTE 52	
111.3	Sta 7+77.5	- Sta 8+22.5 42" PRC Pipe Culvert Crossing
111	Sub-total - Ogle County	
521	Grand Total (Carrdl and Ogle Counties)	

44201421 CLASS C PATCHES, TYPE IV, 15 INCH

SQ YD	LOCATION	REMARKS
	Ogle County	
	US RTE 52	
122.8	Sta 65+80	- Sta 66+30 Existing Triple 10'x6' Box Culvert
159.6	Sta 178+50	- Sta 179+15 Twin 36" Pipe Culvert Crossing
165.6	Sta 187+27	- Sta 187+94 36" Pipe Culvert Crossing
113.8	Sta 203+16.7	- Sta 203+62.2 60" Arch Pipe Culvert Equiv. Crossing
77.6	Sta 327+10	- Sta 327+41 36" Pipe Culvert Crossing
639	Total - Ogle County	

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

EACH	LOCATION	REMARKS
	Carroll County	
	Existing Brookville Road	
1	Sta 122+25.8	- 2'x2' Box Culvert w/ Headwalls
1	Total (Carrdl County)	

50100400 REMOVAL OF EXISTING STRUCTURES NO. 2

EACH	LOCATION	REMARKS
	Ogle County	
	IL RTE 64	
1	Sta 2+40.8	- Pipe Culvert w/ Headwall
1	Total (Ogle County)	

50100500 REMOVAL OF EXISTING STRUCTURES NO. 3

EACH	LOCATION	REMARKS
	Ogle County	
	US RTE 52	
1	Sta 7+81.2	- 2'x2' Box Culvert w/ Headwalls
1	Total (Ogle County)	

50100600 REMOVAL OF EXISTING STRUCTURES NO. 4

EACH	LOCATION	REMARKS
	Carroll County	
	US RTE 52/IL RTE 64	
1	Sta 1507+30	- Across road pipe culvert
1	Total (Carrdl County)	

50100700 REMOVAL OF EXISTING STRUCTURES NO. 5

EACH	LOCATION	REMARKS
	Carroll County	
	US RTE 52/IL RTE 64	
1	Sta 1508+00	- Across road pipe culvert
1	Total (Carrdl County)	

50100800 REMOVAL OF EXISTING STRUCTURES NO. 6

EACH	LOCATION	REMARKS
	Carroll County	
	US RTE 52/IL RTE 64	
1	RT Sta 1507+30	- Across Ex. Brookville Road
1	Total (Carrdl County)	

PLOT DATE: Wed Mar 87 13:18:37 2007  
 FILE NAME: c:\projects\420265\420265.dgn  
 PLOT SCALE: 1/8" = 1'-0"  
 USER NAME: c:\dmsd

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>FAS ROUTE 2079 (US 52)</b> <b>SECTION (16,17,18)RS-3 &amp; (16BR)M-1</b> <b>CARROLL &amp; OGLE COUNTIES</b> SCALE: VERT.      DRAWN BY HORIZ.              CHECKED BY DATE

**SCHEDULE OF QUANTITIES**