

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*2079	**	CARROLL & OGLE	232	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(US 52)		**(16,17,18)RS-3 & (16BR)M-1		

SCHEDULE OF QUANTITIES

54213471 END SECTIONS 36"

EACH	LOCATION
1	Carroll County Brookville Road RT Sta 130+00
1	Total - Carrdl County

550A0070 STORM SEWERS, CLASS A, TYPE 1 15"

FOOT	LOCATION	REMARKS
51.3	Carroll County US RTE 52 Sta 1510 +00	Across Roadway
52	Total - Carrdl County	

63500105 DELINEATORS

EACH	LOCATION
2	Carroll County US RTE 52/IL RTE 64 Sta 1502+64.6
1	US RTE 52 Sta 1510+00
2	IL RTE 64 Sta 1512+18
2	IL RTE 64 Sta 1511+16
2	Brookville Road RT/LT Sta 122+40
2	LT Sta 124+45
2	LT Sta 125+15
2	RT/LT Sta 130+00
2	Ogle Road LT Sta 160+51
17	Sub-total - Carrdl County

54213660 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"

EACH	LOCATION
1	Carroll County US RTE 52 RT Sta 1510 +00
1	Total - Carrdl County

60600095 CLASS SI CONCRETE (OUTLET)

CU YD	LOCATION	REMARKS
1.23	Carroll County US RTE 52/IL RTE 64 LT Sta 1500 +53.66	- Sta 1500 +65.66
3.49	LT Sta 1504 +76.06	- Sta 1505 +17.29
3.49	US RTE 52 LT Sta 1511 +07.62	- Sta 1511 +49
8.2	Sub-total - Carrdl County	

2	RT/LT Sta 122+40
2	LT Sta 124+45
2	LT Sta 125+15
2	RT/LT Sta 130+00
2	Ogle Road LT Sta 160+51
17	Sub-total - Carrdl County

54213681 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"

EACH	LOCATION
2	Ogle County US RTE 52 Sta 327 +83.3
2	Total - Ogle County

3.49	Ogle County IL RTE 64 RT Sta 0 +26.90	- Sta 0 +69.10
1.23	Eldorado Street RT Sta 598+88.21	- Sta 599+00.21
3.10	RT Sta 599+14.18	- Sta 599+44.21
7.8	Sub-total - Ogle County	
16.0	Grand Total (Carrdl and Ogle Counties)	

2	Ogle County US RTE 52 RT Sta 0+18
2	LT Sta 4+00
2	RT/LT Sta 8+00
2	RT/LT Sta 178+82
2	RT/LT Sta 187+50
2	RT/LT Sta 203+39
2	RT/LT Sta 327+83.3
2	IL RTE 64 RT/LT Sta 2+40.65
2	Ogle Road LT Sta 158+98
2	RT/LT Sta 162+00
2	Eldorado Street LT Sta 599+13
2	RT/LT Sta 599+50
2	Taylor Street RT/LT Sta 999+55.8
26	Sub-total - Carrdl County
43	Grand Total (Carrdl and Ogle Counties)

54214299 END SECTIONS, EQUIVALENT ROUND-SIZE 24"

EACH	LOCATION
2	Ogle County Taylor Street RT/LT Sta 999+55.8
2	Total - Ogle County

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	REMARKS
100	Ogle County US RTE 52 RT Sta 178+00	- Sta 179+00
100	LT Sta 178+36	- Sta 179+36
150	LT Sta 187+16	- Sta 188+66
100	RT Sta 202+73	- Sta 203+73
100	LT Sta 203+00	- Sta 204+00
550	Total - Ogle County	

54214929 PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 24"

EACH	LOCATION
2	Ogle County IL RTE 64 Sta 2 +40.65
2	Total - Ogle County

54215430 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"

EACH	LOCATION	REMARKS
2	Carroll County Brookville Road Sta 122+40	See Highway Standard 542201
2	Total - Carrdl County	

54215436 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"

EACH	LOCATION	REMARKS
1	Ogle County US RTE 52 LT Sta 187+50	See Highway Standard 542201
1	Total - Carrdl County	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		FAS ROUTE 2079 (US 52) SECTION (16,17,18)RS-3 & (16BR)M-1 CARROLL & OGLE COUNTIES SCALE: VERT. _____ HORIZ. _____ DATE _____

SCHEDULE OF QUANTITIES

PLOT DATE = Wed Mar 07 13:53:37 2007
 FILE NAME = c:\p\proj\mass\ad2020665\2020665.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = dmsdd