CONTRACT NO. 64237

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*2079	**	CARROLL&OGLE	232	26
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(US 52) **(16,17,18)RS-3 & (16BR)M-1

SCHEDULE OF QUANTITIES

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

FOOT	LOCATION
	US RTE 52/IL RTE 64
41.7	Sta 1495 +60 - Sta 1508 +10
	US RTE 52
11.8	Sta 1509 +60 - Sta 1513 +15
	IL RTE 64
7.4	Sta 1509 +21 - Sta 1511 +43.77
	Brookvile Road
42.5	Sta 117 +75 - Sta 130 +50
103	Sub-total - Carrdl County
	Ogle County
	US RTE 52
1084.2	Sta 0 +00 - Sta 325 +25
	IL RTE 64
13.3	Sta 0 +00 - Sta 4 +00
1098	Sub-total - Ogle County
1201	Grand Total (Carrdl and Ogle Counties)

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT		LOCATION	OFFSET	REMARKS
		Carroll County		
		US RTE 52/IL RTE 64		
15.6	RT	Sta 1504 +79.63	4.65'	White Left Arrow
15.6	RT	Sta 1505 +57.16	4.65'	White Left Arrow
15.6	RT	Sta 1506 +34.68	4.65'	White Left Arrow
15.6	RT	Sta 1507 +12.13	4.65'	White Left Arrow
15.6	RT	Sta 1507 +89.63	4.65'	White Left Arrow
15.6	RT	Sta 1509 +81.37	9.35'	White Left Arrow
15.6	RT	Sta 1510 +18.87	9.35'	White Left Arrow
15.6	RT	Sta 1510 +56.37	9.35'	White Left Arrow
125		Total (Carrdl County)		

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT		LOCATION	REMARKS
		Carroll County	
		US RTE 52/IL RTE 64	
1178.3	LT	Sta 1495+60 - Sta 1507+38.34	White Edge Line
1216.0	RT	Sta 1495+60 - Sta 1507+76.03	White Edge Line
30.0		Sta 1495+60 - Sta 1496 +89.63	Yellow Skip Dash
3562.2		Sta 1496 +89.63 - Sta 1508 +09.63	Median Double Yellow
167.5	LT	Sta 1507+38.34 - Sta 1509 +44.5	LT White Edge Line - Radius
89.0	RT	Sta 1507 +76.03 - Sta 130 +09.16	LT White Edge Line - Radius
402.8	RT	Sta 1509 +12.16 - Sta 1513 +15	White Edge Line
1118.6		Sta 1509 +61.37 - Sta 1513 +15	Median Double Yellow
337.5	LT	Sta 1509 +77.54 - Sta 1513 +15	White Edge Line
		IL RTE 64	
50.0		Sta 1509 +21.02 - Sta 1511 +43.77	Yellow Skip Dash
199.3	LT	Sta 1509 +44.5 - Sta 1511 +43.77	White Edge Line
184.4	RT	Sta 1509 +59.4 - Sta 1511 +43.77	White Edge Line
85.4	RT	Sta 1509 +59.4 - Sta 1509 +77.54	LT White Edge Line - Radius
		Brookvile Road	
320.0		Sta 117 +75 - Sta 130 +50.34	Yellow Skip Dash
1234.2	LT	Sta 117 +75 - Sta 130 +09.16	White Edge Line
1262.8	RT	Sta 117 +75 - Sta 130 +37.80	White Edge Line
57.8	RT	Sta 130 +37.80 - Sta 1509 +12.16	RT White Edge Line - Radius
11,496		Sub-Total (Carrdl County)	
		Ogle County	
		US RTE 52	
196.1	RT	Sta 0 + 0.00 - Sta 162 + 37.61	LT White Edge Line
1948.5	LT	Sta 0 + 0.00 - Sta 19 + 48.50	White Edge Line
592.3		Sta 0 + 0.00 - Sta 1 + 52.44	Median Double Yellow
123.0		Sta 2 + 19.85 - Sta 2 + 81.37	Median Double Yellow
827.4		Sta 2 + 81.37 - Sta 11 + 8.80	Yellow No Passing Zone-EB
		IL RTE 64	
100.0		Sta 0 + 0.00 - Sta 4 + 0.00	Yellow Skip Dash
800.0		Sta 0 + 0.00 - Sta 4 + 0.00	White Edge Line
		Ogle Road	
432.6	LT	Sta 158 + 05 - Sta 162 + 37.61	White Edge Line
410.5	RT	Sta 158 + 05 - Sta 162 + 15.54	White Edge Line
796.3	RT	Sta 162 + 15.54 - Sta 999 + 28.31	LT White Edge Line (Ogle to Taylor St.)
		Taylor Street	
566.8	RT	Sta 999 + 28.31 - Sta 14 + 70.00	RT White Edge Line
6,794		Sub-Total (Ogle County)	
18,290		Grand Total (Carrdl and Ogle Counties)	

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT		LOCATION	REMARKS
		Carroll County	
		US RTE 52/IL RTE 64	
350.0	RT	Sta 1504 +59.63 - Sta 1508 +09.63	White Edge Line - 14' o/s
115.0		Sta 1509 +61.37 - Sta 1510 +76.37	White Edge Line
465		Total (Carrdl County)	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	REMARKS
	Carroll County	
	US RTE 52/IL RTE 64	
203.8	Sta 1497 +00 - Sta 1504 +48.7	Yellow Diagonal
68.7	Sta 1510 +90.17 - Sta 1513+04.75	Yellow Diagonal
272	Sub-Total (Carrdl County)	
	Ogle County	
41.6	Sta 0 +06.69 - Sta 1+45.2	Yellow Diagonal
5.2	Sta 2 +24.9 - Sta 2+62.1	Yellow Diagonal
47	Sub-Total (Ogle County)	
319	Grand Total (Carrdl and Ogle Counties)	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAS ROUTE 2079 (US 52)

SECTION (16,17,18)RS-3 & (16BR)M-1

CARROLL & OGLE COUNTIES

SCALE: VERT. HORIZ. DRAWN BY

DATE CHECKED BY

PLOT DATE = Wed Mar 07 13:18:38 2007
FILE NAME = c:\pw_work\pw_12\d0268580\d0268580sht-dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = dossdd