

BITUMINOUS SCHEDULE

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*2079	**	CARROLL & OGLE	232	30
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
*(US 52) ** (16,17,18)RS-3 & (16BR)M-1				

US 52/IL 64/SIDERoads

STATIONS	REMARKS	LENGTH FT.	PROPOSED SURFACE AREAS						BIT. PRIME 2 APPLICATIONS TON	AGGREGATE PRIME TON	LEVELING BINDER (HAND METHOD), N50 TON	LEVELING BINDER (MACHINE METHOD), N50 (1.5" FOR CALCS.) TON - 1 1/4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 TON - 2 1/4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 TON - 3"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 TON - 7 1/4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 TON - 10 1/4"	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 TON - 1 1/2"	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 TON - 2"	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 TON - 3"	INCIDENTAL HOT-MIX ASPHALT SURFACING TON	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2" SO. YD.	STRIP REFLECTIVE CRACK CONTROL TREATMENT FOOT	AGG SHLDS. TYPE B - WEDGE (FACTOR OF 1.5) TON	HOT-MIX ASPHALT SHOULDERS, 6" SO. YD.
			PAVEMENT			SHOULDER																		
			EXISTING AREA SO. YD.	WIDENING AREA SO. YD.	OVERALL AREA SO. YD.	BIT. AREA SO. YD.	AGG. AREA SO. YD.																	
CARROLL COUNTY																								
US 52/IL 64																								
1495+60 - 1500+53.38	TAPER/3R PORTION	493.38	1090.1	268.1	1358.2	---	316.3	0.78	2.04	---	114.09	171.14	---	108.84	---	114.09	---	---	---	---	986.76	162.09	---	
1500+53.38 - 1505+00.00	3R PORTION	446.62	1262.4	679.0	1941.4	142.0	128.0	1.19	2.91	---	175.01	262.51	---	333.32	---	175.01	---	---	---	---	893.24	65.60	---	
BROOKVILLE ROAD																								
117+75.00 - 128+95.24	3R PORTION	1120.24	---	---	3236.3	---	693.9	1.85	4.85	---	---	---	634.3	---	---	---	---	---	---	---	---	355.61	---	
IL 64																								
1508+91.52 - 1511+43.77	3R PORTION	252.25	---	---	1126.4	209.8	---	0.76	1.69	---	---	---	---	646.58	---	149.66	---	---	---	---	---	---	209.8	
US 52																								
1505+00.00 - 1511+43.62	3R PORTION	631.62	1674.0	2095.4	3769.4	168.9	126.8	2.25	5.65	---	330.82	496.22	---	850.73	---	330.82	---	---	---	---	1263.24	64.96	---	
1511+43.62 - 1513+15.00	3R PORTION	183.38	458.7	282.0	740.6	---	98.6	0.42	1.11	---	62.21	93.32	---	114.47	---	62.21	---	---	---	---	366.76	50.54	---	
GOOD NEIGHBOR ROADS																								
SEE SCHEDULE		---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	107	---
ENTRANCES		---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
OGLE COUNTY																								
IL 64																								
0+00 - 0+51.36	3R PORTION	51.36	---	---	148.4	34.2	---	0.10	0.22	---	---	---	---	---	85.16	---	20.45	---	---	---	---	---	34.2	
0+51.36 - 4+00	3R PORTION	348.64	---	---	1007.2	---	194.6	0.58	1.51	---	---	---	---	---	578.12	---	112.80	---	---	---	---	99.74	---	
US 52																								
0+00 - 3+21.37	3R PORTION	321.37	783.7	287.5	1071.3	---	160.7	0.61	1.61	---	89.99	134.98	---	116.74	---	89.99	---	---	---	---	642.74	82.36	---	
3+21.37 - 11+00	3R PORTION	778.63	1900.9	467.9	2368.8	---	460.0	1.36	3.55	---	198.98	298.47	---	189.99	---	198.98	---	---	---	---	1551.26	235.77	---	
11+00 - 24+04	3P PORTION	1304.00	3187.6	---	3187.6	289.8	---	1.99	4.78	2.47	340.78	---	---	---	---	292.10	---	---	---	2992.0	1304.00	---	---	
ELKHORN BRIDGE																								
27+24.00 - 145+00.00	3P PORTION	11776.00	28785.8	---	28785.8	2616.9	---	17.97	43.18	22.30	3077.46	---	---	---	---	2637.82	---	---	---	28785.8	11776.00	---	---	
145+00.00 - 146+15.00	3P PORTION	175.00	427.8	---	427.8	38.9	---	0.27	0.64	0.33	45.13	---	---	---	---	39.20	---	---	---	427.8	175.00	---	---	
146+15.00 - 320+52.99	3P PORTION	1737.99	42479.5	---	42479.5	3861.8	---	26.52	63.72	32.91	4541.45	---	---	---	---	3832.67	---	---	---	42479.5	1737.99	---	---	
BUFFALO BRIDGE OMISSION																								
321+92.59 - 335+25.00	3P PORTION	1332.41	3257.0	---	3257.0	296.1	---	2.03	4.89	2.52	348.20	---	---	---	---	298.46	---	---	---	3257.0	1332.41	---	---	
OGLE ROAD																								
158+04.95 - 162+15.68	3R PORTION	410.73	---	---	1247.0	64.3	126.7	0.75	1.87	---	---	---	---	---	---	---	7.20	---	---	---	244.42	---	64.92	64.3
ELDORADO STREET																								
597+88.22 - 600+25.00	3R PORTION	236.78	---	---	343.2	---	49.3	0.20	0.51	---	---	---	---	---	---	---	---	---	---	---	67.28	---	25.27	---
TAYLOR STREET																								
997+84.07 - 999+61.82	3R PORTION	177.75	---	---	444.1	---	---	0.25	0.67	---	---	---	---	---	---	---	---	---	---	---	87.05	---	---	---
W. YOUNG STREET																								
	3P PORTION	---	94.1	---	94.1	---	---	0.05	0.14	---	---	---	---	---	---	---	---	---	---	---	14.49	94.1	---	---
W. CHAMBERS STREET																								
	3P PORTION	---	92.1	---	92.1	---	---	0.05	0.14	---	---	---	---	---	---	---	---	---	---	---	14.19	92.1	---	---
N. BROOKVILLE ROAD																								
	3P PORTION	---	71.1	---	71.1	---	---	0.04	0.11	---	---	---	---	---	---	---	---	---	---	---	10.96	71.1	---	---
N. EAGLE CREEK ROAD																								
	3P PORTION	---	263.4	---	263.4	---	---	0.15	0.40	---	---	---	---	---	---	---	---	---	---	---	40.56	263.4	---	---
GOOSE HOLLOW ROAD																								
	3P PORTION	---	132.9	---	132.9	---	---	0.08	0.20	---	---	---	---	---	---	---	---	---	---	---	20.46	132.9	---	---
N. MT. VERNON ROAD																								
	3P PORTION	---	147.1	---	147.1	---	---	0.08	0.22	---	---	---	---	---	---	---	---	---	---	---	22.65	147.1	---	---
W. CANANA ROAD																								
	3P PORTION	---	121.5	---	121.5	---	---	0.07	0.18	---	---	---	---	---	---	---	---	---	---	---	18.71	---	---	---
E. CANANA ROAD																								
	3P PORTION	---	122.6	---	122.6	---	---	0.07	0.18	---	---	---	---	---	---	---	---	---	---	---	18.88	---	---	---
W. STEWART ROAD																								
	3P PORTION	---	199.6	---	199.6	---	---	0.11	0.30	---	---	---	---	---	---	---	---	---	---	---	30.74	---	---	---
N. FREEPORT ROAD																								
	3P PORTION	---	429.8	---	429.8	---	---	0.25	0.64	---	---	---	---	---	---	---	---	---	---	---	66.18	429.8	---	---
S. FREEPORT ROAD																								
	3P PORTION	---	505.2	---	505.2	---	---	0.29	0.76	---	---	---	---	---	---	---	---	---	---	---	77.80	505.2	---	---
S. GALENA TRAIL ROAD																								
	3P PORTION	---	420.3	---	420.3	---	---	0.24	0.63	---	---	---	---	---	---	---	---	---	---	---	64.72	---	---	---
W. ROBIN ROAD																								
	3P PORTION	---	473.7	---	473.7	---	---	0.27	0.71	---	---	---	---	---	---	---	---	---	---	---	72.95	---	---	---
S. SUMMER HILL ROAD																								
	3P PORTION	---	124.2	---	124.2	---	---	0.07	0.19	---	---	---	---	---	---	---	---	---	---	---	19.13	124.2	---	---
GOOD NEIGHBOR ROADS																								
SEE SCHEDULE		---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	159	---
ENTRANCES		---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
SUB-TOTAL-CARROLL COUNTY			4,485	3,324	12,172	521	1,364	9.3	18	0	682	1,023	634	1,407	647	682	150	634	417	0	3,510	805	210	
SUB-TOTAL-OGLE COUNTY			84,020	755	87,965	7,202	1,127	58.7	132	61	8,643	433	0	307	663	7,449	140	0	1,649	79,802	34,165	694	99	
GRAND TOTAL			88,505	4,080	100,138	7,723	2,491	68.0	150	61	9,325	1,457	634	5,115	1,714	8,131	290	634	2,066	79,802	37,675	1,499	309	

PLOT DATE = Thu Mar 08 09:44:49 2007
 PLOT SCALE = 1" = 200'
 USER NAME = dazsdd

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAS ROUTE 2079 (US 52)

SECTION (16,17,18)RS-3 & (16BR)M-1

CARROLL & OGLE COUNTIES

SCALE: VERT. _____ HORIZ. _____ DATE _____ DRAWN BY _____ CHECKED BY _____

BITUMINOUS SCHEDULE