

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*2079	**	CARROLL & OGLE	232	33
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*(US 52)		**(16,17,18)RS-3 & (16BR)M-1		

ENTRANCE SCHEDULE

STATIONING	REMARKS	PROPOSED SURFACE AREA SQ. YD.	35101400	40600200	40800050	42300300
			AGGREGATE BASE COURSE TYPE B TON	BITUMINOUS PRIME TON	INCIDENTAL HOT-MIX ASPHALT SURFACING TON	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH SQ. YD.
CARROLL COUNTY						
US 52/IL 64						
1500 + 92	LT CE	99.5	---	---	---	99.5
1502 + 64.6	RT FE	146.8	66.90	---	---	---
1504 + 47	LT CE	65.2	---	---	9.13	65.2
IL 64						
1510 + 59	RT PE/MB	85.8	---	---	---	85.8
1511 + 16	LT FE	122.8	55.95	---	---	---
US 52						
1512 + 18.37	LT FE	165.1	75.20	---	---	---
BROOKVILLE ROAD						
122 + 37.7	LT PE/MB	327.9	149.36	0.09	45.90	---
124 + 44.42	LT PE	267.9	122.03	0.08	37.50	---
125 + 14.91	LT FE	434.8	198.09	---	---	---
OGLE COUNTY						
US 52						
0 + 18	RT FE	167.0	76.09	---	---	---
4 + 00	LT FE	175.4	79.90	---	---	---
30 + 10	LT PE	90.0	---	0.03	13.87	---
30 + 25	RT FE	155.3	8.85	---	---	---
31 + 15	LT FE	56.5	3.22	---	---	---
31 + 25	RT PE	53.3	---	0.02	8.20	---
32 + 00	RT FE	23.2	1.32	---	---	---
45 + 25	LT PE/MB	84.3	---	0.02	12.97	---
45 + 30	RT FE	14.5	0.83	---	---	---
46 + 05	LT FE	52.7	3.00	---	---	---
62 + 90	LT FE	11.9	0.68	---	---	---
62 + 90	RT FE	14.2	0.81	---	---	---
70 + 40	RT FE	32.3	1.84	---	---	---
103 + 35	LT FE	8.0	0.46	---	---	---
108 + 75	LT FE	9.9	0.56	---	---	---
111 + 50	RT FE	11.5	0.66	---	---	---
125 + 75	LT FE	11.4	0.65	---	---	---
125 + 75	RT PE	57.0	---	0.02	8.77	---
134 + 25	LT PE	66.9	---	0.02	10.30	---
136 + 55	RT FE	14.0	0.80	---	---	---
145 + 75	RT FE	138.8	7.90	---	---	---
146 + 80	LT PE	44.1	---	0.01	6.78	---
200 + 55	LT FE	12.8	0.73	---	---	---
205 + 75	LT MB	31.9	---	0.01	4.91	---
205 + 75	RT PE	44.4	---	0.01	6.84	---
216 + 10	LT PE/MB	70.4	---	0.02	10.85	---
216 + 10	RT FE	9.9	0.56	---	---	---
221 + 45	LT FE	7.0	0.40	---	---	---
230 + 75	RT FE	10.0	0.57	---	---	---
234 + 03	LT FE	9.1	0.52	---	---	---
239 + 02	RT FE	20.0	1.14	---	---	---
244 + 10	LT PE	74.3	---	0.02	11.44	---
245 + 08	LT PE	10.2	---	0.00	1.58	---
245 + 08	RT FE	9.0	0.51	---	---	---
246 + 25	LT PE/MB	121.8	---	0.03	18.75	---
251 + 50	RT FE	13.0	0.74	---	---	---
285 + 75	LT PE/MB	73.2	---	0.02	11.28	---
285 + 75	RT PE	32.7	---	0.01	5.03	---
296 + 10	RT FE	8.0	0.45	---	---	---
303 + 95	RT FE	10.8	0.61	---	---	---
308 + 85	LT PE	73.1	---	0.02	11.26	---
309 + 75	LT PE	27.6	---	0.01	4.25	---
326 + 87	RT FE	137.4	62.59	---	---	---
IL 64						
2 + 86	LT PE/MB	143.3	65.27	0.04	20.06	---
OGLE ROAD						
159 + 00	RT FE	126.9	57.81	---	---	---
160 + 51	LT FE	107.1	48.78	---	---	---
161 + 26	LT PE/MB	126.2	57.51	0.04	17.67	---
ELDORADO STREET						
598 + 60	RT PE	35.7	---	---	---	35.7
599 + 13	LT PE	65.2	29.72	0.02	9.13	---
SUB-TOTAL-CARROLL COUNTY			668	0.17	93	250
SUB-TOTAL-OGLE COUNTY			515	0.37	194	36
GRAND TOTAL			1,183	0.54	286	286

EXCAVATING AND GRADING EXISTING SHOULDER SCHEDULE

STATIONING	OFFSET	DISTANCE FEET	20200600 EXCAVATING AND GRADING EXISTING SHOULDER		
			UNIT	UNIT	
OGLE COUNTY					
US 52					
11+50	-	14+75	RT	326	3.26
11+50	-	24+04	LT	1,254	12.54
15+25	-	24+04	RT	679	6.79
27+24	-	37+10	RT	996	9.96
27+24	-	44+90	LT	1,786	17.86
38+20	-	139+60	RT	10,140	101.40
46+40	-	70+10	LT	2,370	23.70
70+90	-	132+90	LT	6,200	62.00
134+80	-	140+00	LT	520	5.20
140+15	-	176+00	RT	3,585	35.85
141+00	-	176+00	LT	3,500	35.00
190+50	-	201+00	LT	1,060	10.60
190+50	-	189+75	RT	825	8.25
200+00	-	201+00	LT	100	1.00
205+80	-	210+30	RT	480	4.80
205+80	-	211+00	RT	550	5.50
211+75	-	283+75	LT	7,200	72.00
212+10	-	271+50	RT	5,940	59.40
272+90	-	281+80	RT	890	8.90
283+15	-	323+00	RT	3,685	36.85
284+25	-	323+00	LT	3,875	38.75
330+50	-	335+25	LT	475	4.75
330+50	-	335+25	RT	475	4.75
TOTAL				574	

PLOT DATE = Wed Mar 07 13:18:39 2007
 FILE NAME = c:\p\proj\15\262585\82655v.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = dssd

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAS ROUTE 2079 (US 52) SECTION (16,17,18)RS-3 & (16BR)M-1 CARROLL & OGLE COUNTIES SCALE: VERT. _____ HORIZ. _____ DATE _____
NAME	DATE	
		DRAWN BY _____ CHECKED BY _____

ENTRANCE SCHEDULE