

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#595	5HBR	ROCKISLAND	139	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\*(IL 5)

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	IL 92/IL 5 J000 80% FED 20% STATE	IL 84 J000 80% FED 20% STATE	BRIDGE X271-2A 80% FED 20% STATE	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	12	8		
78200520	BARRIER WALL MARKERS, TYPE B	EACH	114	114			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	2	2		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1912	1912			
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	185			185	
X0321100	GEOTEXTILE RETAINING WALL	SQ FT	1362			1362	
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	396	396			
X0320547	REMOVE AND REINSTALL END SECTION	EACH	1	1			
X0323030	DRAINAGE SCUPPERS, DS-11	EACH	2			2	
X0696000	BRIDGE DRAINAGE SYSTEM	L SUM	1			1	
X0712400	TEMPORARY PAVEMENT	SQ YD	760	760			
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	760	760			
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	338	338			
Z0674000	TRAINERS	Hour	500	500			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0017100	DOWEL BARS	EACH	540	540			
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	404	404			
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	70	70			
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2	2			
Z0030020	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2		2		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	5	1	4		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	5	1	4		
Z0065752	SLOTTED DRAIN WITH 6" SLOT	FOOT	200	200			
Z0075300	TIE BARS	EACH	68	68			
B2005214	TREE, MALUS SUTYZAM (SUGAR TYME CRAB APPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	24	24			
X0325875	OSTERBERG LOAD CELL TEST	EACH	1			1	
* 81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	128			128	
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	20			20	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	237			237	
* 81603035	UNIT DUCT, 600V, 2-1C NO.6, 11C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	486			486	
* 83600310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	6.5			6.5	
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1			1	
* X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1			1	
* X0323651	REMOVE AND REINSTALL EXISTING LIGHTING UNIT	EACH	1			1	

△

\* SPECIALTY ITEMS  
# Y080

△ - Revised 11-6-07

PLOT DATE = Thu Sep 20 14:58:18 2007  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = costallog

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 DATE: \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_