

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120T-2	OGLE	59	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNIT	ROADWAY - Y007	
			TOTAL QUANTITY	80% FED 20% STATE
54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'	FOOT	96	96
542D1087	PIPE CULVERTS, CLASS D, TYPE 2 42"	FOOT	125	125
54213477	END SECTIONS 42"	EACH	2	2
60246540	INLET BOX, SPECIAL	EACH	1	1
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	40	40
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	1,088	1,088
63500105	DELINEATORS	EACH	4	4
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	22	22
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	2
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4,230	4,230
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	62	62
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,534	1,534
70400100	TEMPORARY CONCRETE BARRIER	FOOT	660	660

PLOT DATE = Mon, Jul 30, 10:47:41, 2007
 FILE NAME = c:\p\projects\218688\218688.dgn
 PLOT SCALE = 0.00000 / IN.
 USER NAME = dmsdd

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY