

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120T-2	OGLE	59	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION
	IL 72
233.3	Sta 2108+00 - 2109+50 RT (150' X 14')
311.1	Sta 2109+50 - 2111+50 RT (200' X 14')
311.1	Sta 2130+00 - 2132+00 LT (200' X 14')
233.3	Sta 2131+00 - 2132+50 RT (150' X 14')
<u>1088.8</u>	TOTAL

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION
	IL 72
64	Sta 2106+80 - 2112+20 LT
60	Sta 2106+80 - 2112+20 RT
48	Sta 2128+80 - 2134+20 LT
44	Sta 2128+80 - 2134+20 RT
<u>216</u>	TOTAL

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION
	IL 72
1	Sta 2108+00 RT
1	Sta 2108+30 RT
1	Sta 2108+60 RT
1	Sta 2108+85 RT
1	Sta 2109+25 RT
1	Sta 2109+50 RT
1	Sta 2110+00 RT
1	Sta 2110+50 RT
1	Sta 2111+00 RT
1	Sta 2130+25 LT
1	Sta 2130+60 LT
1	Sta 2130+95 LT
1	Sta 2131+30 LT
1	Sta 2131+65 LT
1	Sta 2132+00 LT
1	Sta 2131+25 RT
1	Sta 2131+75 RT
1	Sta 2132+25 RT
<u>18</u>	TOTAL

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION
	IL 72
285	Sta 2109+00 - 2111+50 LT
140	Sta 2130+00 - 2131+25 RT
145	Sta 2132+00 - 2133+25 LT
<u>570</u>	TOTAL

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION
	IL 72
1	Sta 2109+46 47' RT
1	Sta 2131+29 34' RT
<u>2</u>	TOTAL

28100107 STONE RIPRAP, CLASS A4

SQ YD	LOCATION
	IL 72
58.7	Sta 2109+97 LT (24' x 22')
74.7	Sta 2132+18 LT (24' x 28')
<u>133.4</u>	TOTAL

28200200 FILTER FABRIC

SQ YD	LOCATION
	IL 72
58.7	Sta 2109+97 LT (24' x 22')
74.7	Sta 2132+18 LT (24' x 28')
<u>133.4</u>	TOTAL

35101600 AGGREGATE BASE COURSE, TYPE B 4"

SQ YD	LOCATION
	IL 72
405.8	Sta 2106+80 - 2112+20 Shoulder - LT
405.8	Sta 2106+80 - 2112+20 Shoulder - RT
382.3	Sta 2128+80 - 2133+50 Shoulder - LT
405.8	Sta 2128+80 - 2134+20 Shoulder - RT
<u>1599.7</u>	TOTAL

40600990 TEMPORARY RAMP

SQ YD	LOCATION
	IL 72
7.2	Sta 2109+33 LT (13' x 5')
7.2	Sta 2109+33 RT (13' x 5')
7.2	Sta 2109+97 LT (13' x 5')
7.2	Sta 2109+97 RT (13' x 5')
7.2	Sta 2131+10 LT (13' x 5')
7.2	Sta 2131+10 RT (13' x 5')
7.2	Sta 2132+10 LT (13' x 5')
7.2	Sta 2132+10 RT (13' x 5')
<u>57.6</u>	TOTAL

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50

TON	LOCATION
	IL 72
30.7	Sta 2109+33 - 2110+09 Over Patch
43.7	Sta 2131+10 - 2132+18 Over Patch
5.6	Sta 2106+80 - 2107+70 Shoulder - LT
39.2	Sta 2107+70 - 2111+30 Shoulder - LT
5.6	Sta 2111+30 - 2112+20 Shoulder - LT
5.6	Sta 2106+80 - 2107+70 Shoulder - RT
39.2	Sta 2107+70 - 2111+30 Shoulder - RT
5.6	Sta 2111+30 - 2112+20 Shoulder - RT
5.6	Sta 2128+80 - 2129+70 Shoulder - LT
41.6	Sta 2129+70 - 2133+50 Shoulder - LT
5.6	Sta 2128+80 - 2129+70 Shoulder - RT
39.2	Sta 2129+70 - 2133+30 Shoulder - RT
5.6	Sta 2133+30 - 2134+20 Shoulder - RT
<u>272.8</u>	TOTAL

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

SQ YD	LOCATION
	IL 72
219.6	Sta 2109+33 - 2110+09 (76' x 26')
312.0	Sta 2131+10 - 2132+18 (108' x 26')
<u>531.6</u>	TOTAL

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. HORIZ.
DATE DRAWN BY CHECKED BY