

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	120T-2	OGLE	59	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

48101200 AGGREGATE SHOULDERS, TYPE B

<u>TON</u>	<u>LOCATION</u>
	IL 72
<u>30.0</u>	As needed and directed by the Resident
<u>30.0</u>	TOTAL

48203019 HOT-MIX ASPHALT SHOULDERS, 5 1/2"

<u>SQ YD</u>	<u>LOCATION</u>
	IL 72
40.0	Sta 2106+80 - 2107+70 Shoulder - LT
280.0	Sta 2107+70 - 2111+30 Shoulder - LT
40.0	Sta 2111+30 - 2112+20 Shoulder - LT
40.0	Sta 2106+80 - 2107+70 Shoulder - RT
280.0	Sta 2107+70 - 2111+30 Shoulder - RT
40.0	Sta 2111+30 - 2112+20 Shoulder - RT
40.0	Sta 2128+80 - 2129+70 Shoulder - LT
297.0	Sta 2129+70 - 2133+50 Shoulder - LT
40.0	Sta 2128+80 - 2129+70 Shoulder - RT
280.0	Sta 2129+70 - 2133+30 Shoulder - RT
40.0	Sta 2133+30 - 2134+20 Shoulder - RT
<u>1417.0</u>	TOTAL

50100300 REMOVAL OF EXISTING STRUCTURE NO. 1

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>1</u>	Sta 2109+85 (6' x 5.5')
<u>1</u>	TOTAL

50100400 REMOVAL OF EXISTING STRUCTURE NO. 2

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>1</u>	Sta 2131+99 (6' x 4')
<u>1</u>	TOTAL

51500100 NAME PLATES

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>1</u>	Sta 2109+64.78
<u>1</u>	Sta 2131+60
<u>2</u>	TOTAL

54010603 PRECAST CONCRETE BOX CULVERT 6' X 3'

<u>FOOT</u>	<u>LOCATION</u>
	IL 72
<u>144</u>	Sta 2131+60 (Double Cell - 2 @ 72')
<u>144</u>	TOTAL

54010605 PRECAST CONCRETE BOX CULVERT 6' X 5'

<u>FOOT</u>	<u>LOCATION</u>
	IL 72
<u>96</u>	Sta 2109+64.78(Double Cell - 2 @ 48')
<u>96</u>	TOTAL

542D1087 PIPE CULVERTS, CLASS D, TYPE 2 42"

<u>FOOT</u>	<u>LOCATION</u>
	IL 72
<u>60</u>	Sta 2109+85 (Install during Stage 1)
<u>65</u>	Sta 2131+98.8 (Install during Stage 3)
<u>125</u>	TOTAL

54213477 END SECTIONS 42"

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>1</u>	Sta 2109+85 (Install during Stage 1)
<u>1</u>	Sta 2131+98.8 (Install during Stage 3)
<u>2</u>	TOTAL

60246540 INLET BOX, SPECIAL

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>1</u>	Sta 2131 + 29 31' RT (8' X 13.25')
<u>1</u>	TOTAL

61100500 EXPLORATION TRENCH 52" DEPTH

<u>FOOT</u>	<u>LOCATION</u>
	IL 72
<u>40</u>	As directed by the Resident
<u>40</u>	TOTAL

61133100 FIELD TILE JUNCTION VAULTS 2' DIA.

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>4</u>	As directed by the Resident
<u>4</u>	TOTAL

63200310 GUARDRAIL REMOVAL

<u>FOOT</u>	<u>LOCATION</u>
	IL 72
337.5	Sta 2108+83 - 2112+21 LT (27 panels @ 12.5')
312.5	Sta 2107+83 - 2110+96 RT (25 panels @ 12.5')
237.5	Sta 2131+11 - 2133+49 LT (19 panels @ 12.5')
200.0	Sta 2130+74 - 2132+74 RT (16 panels @ 12.5')
<u>1087.5</u>	TOTAL

63500105 DELINEATORS

<u>EACH</u>	<u>LOCATION</u>
	IL 72
<u>1</u>	Sta 2109+64.78LT
<u>1</u>	Sta 2109+64.78RT
<u>1</u>	Sta 2131+60 LT
<u>1</u>	Sta 2131+60 RT
<u>4</u>	TOTAL

PLOT DATE = Mon Jul 30 11:51:15 2007
 FILE NAME = c:\prowork\64218685\dr64b43.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = dssidd

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____
DATE _____		