

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	114 BR	LIVINGSTON	43	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:	
				ROADWAY J000	BRIDGE X020-2A
60240240	INLETS, TYPE B, TYPE 6 FRAME AND GRATE	EACH	1		
60260100	INLETS TO BE ADJUSTED	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
* 63000000	STEEL PLATE GUARD RAIL, TYPE A	FOOT	275	275	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200305	STEEL PLATE GUARD RAIL REMOVAL	FOOT	686	686	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4582	4582	
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	290	290	
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	160	160	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1527	1527	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275	275	
78004100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C-LETTERS AND SYMBOLS	SQ FT	364	364	
78004180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LINE 24"	FOOT	183	183	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	5	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32	32	
78200300	PRISMATIC CURB REFLECTOR	EACH	18	18	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	297	297	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	37	37	
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	150	150	
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	215	215	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	55	55	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	150	150	
XX002134	CONCRETE CURB AND GUTTER OUTLET SPECIAL	EACH	2	2	
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	417	417	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5016	5016	
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1145	1145	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	233	233	
X8430100	REMOVE EXISTING CONDUIT ATTACHED TO STRUCTURE	FOOT	150	150	
Z0005215	BITUMINOUS STABILIZATION 6" AT STEEL PLATE BEAM GUARDRAIL	SQ YD	38.4	38.4	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0038700	PERMANENT BENCH MARKS	EACH	1		1
Z0055300	RUMBLE STRIP	EACH	3	3	

* SPECIALTY ITEMS
 ** SFTY - 3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = Aug 28, 2007 - 09:59:22 AM
 FILE NAME = c:\projects\lgs01103\lgs01103.dgn
 USER NAME = ferguson