

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	114 BR	LIVINGSTON	43	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

REMOVAL SCHEDULE			
LOCATION	PAVEMENT REMOVAL	BITUMINOUS SHOULDER REMOVAL	CONCRETE CURB & GUTTER REMOVAL
STATION	SQ YD	SQ YD	FOOT
STA. 583+00 TO STA. 584+95.5	317	240	
STA. 584+95.5 TO STA. 586+78	332	152	250
TOTAL	649	392	250

APPROACH PAVEMENT						
LOCATION	LENGTH	WIDTH	AREA	BRIDGE APPROACH PAVEMENT	BRIDGE APPROACH PAVEMENT (SPECIAL)	BRIDGE APPR. PVMT. CONNECTOR FLEXIBLE
	FEET	FEET	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.
STA. 584+33 TO STA. 584+39	6	46	30.67			30.67
STA. 584+39 TO STA. 584+69	30	46	153.33	153.33		
STA. 584+69 TO STA. 585+60	91	46	465.11			
STA. 585+60 TO STA. 585+90	30	VAR	167.22		167.22	
STA. 585+90 TO STA. 585+96	6	VAR	33.89			33.89
TOTAL				153.33	167.22	64.56

RAISED REFLECTIVE PAVEMENT MARKERS							
LOCATION	ONE WAY	ONE WAY		TWO WAY	RAISED REF. MRK BRIDGE	PRISMATIC CURB REFLECTORS	REFLECTOR REMOVAL LIN FT
		CRYSTAL LIN FT	AMBER LIN FT	AMBER LIN FT			
LIVINGSTON COUNTY							
	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA. 580+00 TO STA. 583+30	285		15.0				15
STA. 583+30 TO STA. 585+10	180		8.0		2		10
STA. 585+10 TO STA. 586+78	168	3.0		6	3		12
NORTH WEST ISLAND						9	
SOUTH WEST ISLAND						9	
PROJECT TOTAL	3	23	6	5	18	37	

PAVEMENT MARKING SCHEDULE														
LOCATION	LENGTH	POLYUREA PAVEMENT MARKING					PRE-FORMED PLASTIC		TEMPORARY		SHORT TERM PAVEMENT MARKING		PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVT' MK REMOVAL SQ FT
		PAINT PVMT MARKING		PAINT PVMT MARKING	PAINT PVMT MARKING		PAVEMENT MARKING TY. C	PAVEMENT MARKING TY. C LETTERS & SYMBOLS	PAINT PVMT MARKING	PAINT PVMT MARKING	WHITE	YELLOW		
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	FT	FT		
IL 116	FT	4"	4"	8"	12"	12"	24"			8"	12"	FT	FT	
PRE-STAGE CONSTRUCTION														
NORTH LEG		150	300	150			24	124.8						
SOUTH LEG		150	300	150			24	124.8						
EAST LEG		240	200	375	140		67	83.2						
WEST LEG									290	160				
STAGE I											1246	980	297	741.9
STAGE II											1316	1040		785.3
FINAL PAVEMENT MARKINGS														
STA 580+00 TO STA 580+45	45	90	90											
STA 580+45 TO STA 583+30	285	450	1140			75								
STA 583+30 TO STA 585+10	180	360	720	45		42								
STA 585+10 TO STA 586+78	168	566	260	425	160		68	31.2						
LINE TOTAL		2006	3010	1145	300	117	183	364	290	160	2562	2020	297	1527

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____

PLOT DATE = Aug 23, 2007 - 84:25:04 PM
 FILE NAME = c:\p\proj\114\114183\114183.dgn
 PLOT SCALE = 20:1000 - 7 IN.
 USER NAME = rjgarcera