

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	06-BHER	BUREAU	165	61
STA.		TO STA.		
FED. ROAD DIST. NO. 3		ILLINOIS FED. AID PROJECT		

SIGNING SCHEDULE - GROUND MOUNTED SIGNS

SIGN NO.	STATION	LT/RT	SIGN PANELS				TELESCOPING STEEL SIGN SUPPORT				WOOD SIGN SUPPORT			73400100 CONC FOUNDATION (CU.YD.)	73502000 REL GR-MT SIN SUPPORT (EACH)	73700200 REM CONC FDN-CR MT (EACH)	
			"AA" (L.F.)	"BB" (L.F.)	WIDTH (L.F.)	DEPTH (L.F.)	72000100 SIGN PANEL T1 (SQ. FT.)	72400710 RELOC SIGN PANEL T1 (SQ. FT.)	72400720 RELOC SIGN PANEL T2 (SQ. FT.)	72400730 RELOC SIGN PANEL T3 (SQ. FT.)	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)				73000100 PAY LENGTH (L.F.)
TS-1A	228+89	RT	N/A	7.5	2.50	2.50					13.3			16.3			
TS-1B					1.50	0.50					0.75						
TS-1C					2.00	2.50					5.00						
TS-2	234+20	RT	N/A	7.5	2.00	2.50					10.3			13.3			
TS-3	235+51	RT	N/A	7.5	2.00	2.50					10.3			13.3			
TS-4	246+18	LT	N/A	7.5	2.00	2.50					10.3			13.3			
TS-5	249+04	RT	4.70	4.0	2.00	2.50					6.8			11.8			
TS-6	250+32	RT	N/A	7.5	2.00	2.50					10.3			13.3			
TS-7	257+66	RT	N/A	7.5	2.00	2.50					10.3			13.3			
WP-1A	228+80	LT	N/A	7.5	2.50	2.50							15.0			15.0	
WP-1B					1.50	0.50					0.75						
WP-2A	228+65	RT	N/A	7.5	2.50	2.50							15.0			15.0	
WP-2B					1.50	0.50					0.75						
WP-3A	228+78	LT	N/A	7.5	2.50	2.50							15.0			15.0	
WP-3B					1.50	0.50					0.75						
WP-4A	229+03	LT	10.20	7.0	2.50	2.50							15.8			15.8	
WP-4B					1.50	0.50					0.75						
WP-5A	228+99	RT	11.10	7.0	2.50	2.50							15.7			15.7	
WP-5B					1.50	0.50					0.75						
WP-6A	229+65	RT	17.50	7.0	2.50	2.50							16.5			16.5	
WP-6B					3.00	1.50											
WP-7A	230+19	RT	12.96	7.0	2.00	0.83							15.5			15.5	
WP-7B					2.00	2.00					4.00						
WP-8A	230+83	RT	21.88	7.0	1.75	1.25							16.8			16.8	
WP-8B					2.00	2.00											
WP-9A	231+54	LT	17.70	7.0	5.00	3.00			15.00				19.4	19.4		38.8	
WP-9B					5.00	1.50											
WP-10A	232+54	LT	13.11	7.0	2.00	0.83							16.5			16.5	
WP-10B					2.00	2.00											
WP-11A	110+92	RT	13.10	7.0	2.50	2.50							22.9			22.9	
WP-11B					3.00	1.00											
WP-12	110+59	RT	13.43	7.0	2.50	2.50							20.9			20.9	
WP-13A	233+89	LT	N/A	7.5	3.00	1.00							16.5			16.5	
WP-13B					3.00	1.00											
WP-13C					2.50	2.50											
WP-14	110+53	LT	14.10	7.0	2.50	2.50							19.3			19.3	
WP-15A	110+80	LT	13.47	7.0	3.00	1.00							22.2			22.2	
WP-15B					2.50	2.50											
WP-16A	234+74	RT	14.50	13.3	2.00	0.83							15.7			15.7	
WP-16B					2.00	2.00											
WP-16C					1.50	0.83											
WP-17A	235+36	RT	17.40	7.0	2.00	0.83							18.0			18.0	
WP-17B					2.00	2.00											
WP-17C					2.00	1.50											
WP-17D					2.00	0.83											
WP-17E					2.00	2.00											
WP-17F					2.00	1.50											
WP-18A	236+53	LT	17.10	7.0	2.00	0.83							18.0			18.0	
WP-18B					2.00	2.00											
WP-18C					2.00	1.50											
WP-18D					2.00	0.83											
WP-18E					2.00	2.00											
WP-18F					2.00	1.50											
WP-19A	239+31	LT	18.64	7.0	1.75	1.25							19.9			19.9	
WP-19B					2.00	2.00											
WP-20A	243+88	LT	18.50	7.0	2.00	0.83							20.5			20.5	
WP-20B					2.00	2.00											
WP-20C					1.50	0.83											
WP-21A	246+31	LT	15.40	7.0	2.00	0.83							16.1			16.1	
WP-21B					2.00	2.00											
WP-22A	246+64	LT	14.50	7.0	2.00	0.83							16.2			16.2	
WP-22B					2.00	2.00											

PLOT DATE = 8/28/2007
 FILE NAME = g:\pvc\mst\20648851.dwg
 PLOT SCALE = 1/8" = 1' IN.
 USER NAME = zplanud

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL ROUTE 89 OVER I-80

PAVEMENT MARKING AND SIGNING

SCALE: VERT. NONE
 HORIZ. 1" = 20'

DATE: 08/10/07

DRAWN BY ACE/CAD
 CHECKED BY TMH

