

SUMMARY OF QUANTITIES

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	FACTORVILLE (ST. AUSTIN)	MCDONOUGH	66	5
STA.		TO STA.		
D-94-006-07		ALLIANCE	FED. AID PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		055-0006 100% STATE SFTY-2A	055-0018 100% STATE X081-2A
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	12	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	9	6	3
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1604	1604	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	3080		3080
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	535	535	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	520		520
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	520		520
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5130	2050	3080
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10		10
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	12		12
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SO FT	684	684	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10		10
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	139		139
X0321475	PIPE ELBOW, 12"	EACH	4		4
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	139	139	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Z0020800	EROSION CONTROL CURB	Foot	713		713
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0032700	KEYWAY REPAIR	FOOT	25	25	

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES			