

# SCHEDULE OF QUANTITIES - GRINDSTONE CREEK

ROUTE NO. F.A.P. 310 U.S. 67	SECTION (40B)BR, (41-A)BR-1	COUNTY McDonough	TOTAL SHEETS 66	SHEET 12
FED. ROAD DIST. NO. 4			FED. AID PROJECT	
Contract #68677				

TRAFFIC BARRIER TERMINAL, TYPE 6		
STATION	EACH	REMARKS
N.E. BRIDGE GUARDRAIL	1	STANDARD 631031-05
N.W. BRIDGE GUARDRAIL	1	
S.E. BRIDGE GUARDRAIL	1	
S.W. BRIDGE GUARDRAIL	1	
<b>PROJECT TOTAL</b>	<b>4</b>	

63100085

EPOXY PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
LT. STA. 450+30 - STA. 458+00	770	EDGE LINE - WHITE
STA. 450+30 - STA. 458+00	1,540	CENTERLINE - DBL YELLOW
RT. STA. 450+30 - STA. 458+00	770	EDGE LINE - WHITE
<b>PROJECT TOTAL</b>	<b>3,080</b>	

78005110

HMA BINDER COURSE, IL-19.0, N50		
STATION	TON	REMARKS
STA. 451+75+ - STA. 453+40.93	258	AS DIRECTED BY THE ENGINEER
<b>PROJECT TOTAL</b>	<b>258</b>	

40603080

PERMANENT SURVEY MARKERS TYPE I			
STATION	DESC.	EACH	REMARKS
STA. 450+50	POT	1	
STA. 458+00	POT	1	
S.N. 055-0049		1	
<b>PROJECT TOTAL</b>		<b>3</b>	

66700205

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)		
STATION	EACH	REMARKS
N.E. BRIDGE GUARDRAIL	1	STANDARD 630301-03
N.W. BRIDGE GUARDRAIL	1	
S.E. BRIDGE GUARDRAIL	1	
<b>PROJECT TOTAL</b>	<b>3</b>	

63100167

RAISED REFLECTIVE PAVEMENT MARKER		
STATION	EACH	REMARKS
STA. 450+30 - STA. 458+00	10	STANDARD 781001-02
<b>PROJECT TOTAL</b>	<b>10</b>	

78100100

EROSION CONTROL CURB		
STATION	FOOT	REMARKS
LT. STA. 452+14 - STA. 453+51	137	STANDARD 630101-D4
RT. STA. 450+93 - STA. 453+31	238	
LT. STA. 455+09 - STA. 457+47	238	
RT. STA. 454+89 - STA. 455+89	100	
<b>PROJECT TOTAL</b>	<b>713</b>	

20020800

TEMPORARY BRIDGE TRAFFIC SIGNALS		
STATION	EACH	REMARKS
N.E. BRIDGE		
N.W. BRIDGE	1	
S.E. BRIDGE		
S.W. BRIDGE		
<b>PROJECT TOTAL</b>	<b>1</b>	

70106500

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)		
STATION	EACH	REMARKS
S.W. BRIDGE GUARDRAIL	1	STANDARD 630301-03
<b>PROJECT TOTAL</b>	<b>1</b>	

63100169

GUARD RAIL MARKERS, TYPE A		
STATION	EACH	REMARKS
LT. STA. 451+80 - 457+81	6	STANDARD 635011-02
RT. STA. 450+59 - 456+13	6	
<b>PROJECT TOTAL</b>	<b>12</b>	

78200410

IMPACT ATTENUATORS, TEMPORARY (NON REDIRECTIVE) TEST LEVEL 3		
STATION	EACH	REMARKS
STAGE I CONSTRUCTION	2	
<b>PROJECT TOTAL</b>	<b>2</b>	

20030250

STEEL PLATE BEAM GUARD RAIL REMOVAL		
STATION	FOOT	REMARKS
N.E. BRIDGE GUARDRAIL	372	
N.W. BRIDGE GUARDRAIL	368	
S.E. BRIDGE GUARDRAIL	100	
S.W. BRIDGE GUARDRAIL	76	
<b>PROJECT TOTAL</b>	<b>914</b>	

63200305

TERMINAL MARKER - DIRECT APPLIED		
STATION	EACH	REMARKS
RT. STA. 450+93	1	STANDARD 635006-02
LT. STA. 452+14	1	
LT. STA. 457+47	1	
RT. STA. 456+13	1	
<b>PROJECT TOTAL</b>	<b>4</b>	

78201000

IMPACT ATTENUATORS, RELOCATE (NON REDIRECTIVE) TEST LEVEL 3		
STATION	EACH	REMARKS
STAGE I CONSTRUCTION	2	
<b>PROJECT TOTAL</b>	<b>2</b>	

20030350

TEMPORARY PAINT PAVEMENT MARKING LINE 4"		
STATION	FOOT	REMARKS
LT. STA. 450+30 - STA. 458+00	770	EDGE LINE - WHITE
STA. 450+30 - STA. 458+00	1,540	CENTERLINE - DBL YELLOW
RT. STA. 450+30 - STA. 458+00	770	EDGE LINE - WHITE
<b>PROJECT TOTAL</b>	<b>3,080</b>	

70300625

GUARDRAIL AGGREGATE EROSION CONTROL		
STATION	TON	REMARKS
LT. STA. 451+80 - STA. 453+51	28	STANDARD 630001-06
RT. STA. 450+99 - STA. 453+31	45	
LT. STA. 455+09 - STA. 457+81	45	
RT. STA. 454+89 - STA. 456+13	21	
<b>PROJECT TOTAL</b>	<b>139</b>	

X0301612

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
STATION	EACH	REMARKS
STA. 450+30 30' LT	1	
STA. 450+30 55' LT	1	
STA. 451+00 35' RT	1	
STA. 451+00 40' RT	1	
STA. 455+75 35' RT	1	
STA. 455+75 40' RT	1	
STA. 457+30 40' LT	1	
STA. 457+30 55' LT	1	
<b>PROJECT TOTAL</b>	<b>8</b>	

66600105

TEMPORARY CONCRETE BARRIER		
STATION	FOOT	REMARKS
STAGE I CONSTRUCTION	520	
STA. 451+00 - STA. 456+20		
<b>PROJECT TOTAL</b>	<b>520</b>	

70400100

HMA BASE COURSE WIDENING, 10 INCH		
STATION	SQ. YD.	REMARKS
RT. STA. 450+30 - STA. 453+96	81	USED FOR STAGE I TRAFFIC
RT. STA. 454+28 - STA. 455+85	35	
<b>PROJECT TOTAL</b>	<b>116</b>	

X3560140

STEEL PLATE BEAM GUARDRAIL, TYPE A		
STATION	FOOT	REMARKS
N.E. BRIDGE GUARDRAIL	87.5	STANDARD 630001-06
N.W. BRIDGE GUARDRAIL	187.5	
S.E. BRIDGE GUARDRAIL	187.5	
S.W. BRIDGE GUARDRAIL	50	
<b>PROJECT TOTAL</b>	<b>512.5</b>	

63000000

RELOCATE TEMPORARY CONCRETE BARRIER		
STATION	FOOT	REMARKS
STAGE II CONSTRUCTION	520	
STA. 451+00 - STA. 456+20		
<b>PROJECT TOTAL</b>	<b>520</b>	

70400200

HMA SURFACE COURSE, MIX "D", N50		
STATION	TON	REMARKS
STA. 450+30 - STA. 453+40.93	102	AS DIRECTED BY THE ENGINEER
STA. 454+99.07 - STA. 458+00	90	
<b>PROJECT TOTAL</b>	<b>192</b>	

X4066426

TEMPORARY RUMBLE STRIP		
LOCATION	EACH	REMARKS
NORTH PROJECT LIMIT	3	
<b>PROJECT TOTAL</b>	<b>3</b>	

70106700

**SCHEDULE OF QUANTITIES  
F.A.P. 310 SECTION (41A)BR-1  
U.S. ROUTE 67 OVER GRINDSTONE CREEK  
McDONOUGH COUNTY  
STA. 454+20 (S.N. 055-0049)**