CONTRACT NO. 70404

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	CHAMPAIGN	71	6

* 10(33RS-4(34-1,35,36,37)RS-2)

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CHAMPAIGN COUNTY RURAL ROADWAY / STRUCTURE IMPROVEMENTS FAI - 57 STA. 902+84 STA. 1258+09 90% FEDERAL 10% STATE I000-2A QUANTITY	CHAMPAIGN COUNTY URBAN ROADWAY / STRUCTURE IMPROVEMENTS FAI - 57 STA. 544+40 TO STA. 637+33 STA. 1258+09 TO STA. 1070+77.24 90% FEDERAL 10% STATE I000-2A QUANTITY	CHAMPAIGN COUNTY URBAN ROADWAY / STRUCTURE IMPROVEMENTS FAI - 57 STA. 626+66.67 S.N. 010-0100 90% FEDERAL 10% STATE SFTY-2A QUANTITY
44200632	CLASS A PATCHES, TYPE IV, 15 INCH	SQ YD	2,880.0		2880.0	
44201411	CLASS C PATCHES, TYPE I, 15 INCH	SQ YD	11.0		11.0	
44201415	CLASS C PATCHES, TYPE II, 15 INCH	SQ YD	96.0		96.0	
44201423	CLASS C PATCHES, TYPE I, 16 INCH	SQ YD	12.0		12.0	
44201427	CLASS C PATCHES, TYPE II, 16 INCH	SQ YD	146.0		146.0	
44213000	PATCHING REINFORCEMENT	SQ YD	7,826.0	3899.8	3926.2	
44213200	SAW CUTS	FOOT	20,707.0	13,502.0	7205.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5,219.0	120.7	5098.3	
50104000	BRIDGE RAIL REMOVAL	FOOT	664.0			664.0
* 50901105	STEEL RAILING	FOOT	664.0			664.0
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6.0		6.0	
60107600	PIPE UNDERDRAINS 4"	FOOT	4,324.0		4324.0	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	85.0		85.0	
63400105	GUARD POSTS	EACH	163.0	91.0	72.0	
63400205	GUARD POSTS REMOVAL	EACH	149.0	81.0	68.0	
63500105	DELINEATORS	EACH	89.0	66.0	23.0	
63500120	DELINEATOR REMOVAL	EACH	89.0	66.0	23.0	
64200105	SHOULDER RUMBLE STRIP	FOOT	181,189.0	138,944.0	42,245.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6.0	4.0	2.0	
67100100	MOBILIZATION	L SUM	1.0	0.8	0.2	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8.0		8.0	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.8	0.2	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60.0	48.0	12.0	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	24,752.0	18,188.9	6563.1	

1

PLOT DATE = 8/20/2007
FILE NAME = d:\projects\d584684 (db)\70404sht.dgn
PLOT SCALE = 42.2500 ' / IN.
USER NAME = cellinpw

* SPECIALTY ITEM

1 - Revised 10/24/07