

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	120B	MCLEAN	31	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				STRUCTURE 80% FED 20% STATE X071-2A			
20200100	EARTH EXCAVATION	CU YD	60	60			
20300100	CHANNEL EXCAVATION	CU YD	59	59			
20400800	FURNISHED EXCAVATION	CU YD	780	780			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	110	110			
25000200	SEEDING, CLASS 2	ACRE	0.50	0.50			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	48	48			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	48	48			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	48	48			
25100115	MULCH, METHOD 2	ACRE	0.50	0.50			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	53	53			
28000300	TEMPORARY DITCH CHECKS	EACH	4	4			
28000400	PERIMETER EROSION BARRIER	FOOT	538	538			
28100107	STONE RIPRAP, CLASS A4	SO YD	673	673			
28200200	FILTER FABRIC	SO YD	673	673			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	235	235			
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	571	571			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	146	146			
42001300	PROTECTIVE COAT	SO YD	222	222			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO YD	222	222			
42001430	BRIDGE APPROACH PAVEMENT CONNNECTOR (FLEXIBLE)	SO YD	44	44			
44000100	PAVEMENT REMOVAL	SO YD	205	205			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	611	611			
44000700	APPROACH SLAB REMOVAL	SO YD	146	146			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	24	24			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	210	210			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1			
50200100	STRUCTURE EXCAVATION	CU YD	694	694			
50300225	CONCRETE STRUCTURES	CU YD	30.8	30.8			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	112.3	112.3			
50300260	BRIDGE DECK GROOVING	SO YD	267	267			
50300280	CONCRETE ENCASEMENT	CU YD	4.2	4.2			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				STRUCTURE 80% FED 20% STATE X071-2A			
50300300	PROTECTIVE COAT	SO YD	352	352			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1			
50500505	STUD SHEAR CONNECTORS	EACH	1,134	1,134			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24,720	24,720			
50800515	BAR SPLICERS	EACH	64	64			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	640	640			
51202305	DRIVING PILES	FOOT	640	640			
51203600	TEST PILE STEEL HP12X53	EACH	2	2			
51500100	NAME PLATES	EACH	1	1			
52100520	ANCHOR BOLTS, 1"	EACH	24	24			
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	60	60			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	134	134			
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50.0	50.0			
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	484	484			
66500105	WOVEN WIRE FENCE, 4'	FOOT	370	370			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	6			
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,800	1,800			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6			
78200530	BARRIER WALL MARKERS, TYPE C	EACH	2	2			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11	11			
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SO YD	436	436			
20001900	ASBESTOS BEARING PAD REMOVAL	EACH	22	22			
20022800	FENCE REMOVAL	FOOT	376	376			
20037300	PAVEMENT GROOVING	SO YD	186	186			

**LEGEND**

- SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES  
SHEET 1 OF 1**

SCALE: VERT. NONE  
HORIZ. NONE

DRAWN BY:  
CHECKED BY:

DATE: