CONTRACT NO. 70518

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	120B	McLEAN	31	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ITEM NO. 70101800 TRAFFIC CONTROL AND PROTECTION (SPECIAL)

1 LUMP SUM

ITEM NO. 78001110 PAINT PAVEMENT MARKING-LINE 4"

LOCATION	FOOT
YELLOW (SKIP-DASH) CENTERLINE	
STA. 1204+50 TO STA. 1212+50	200
WHITE (EDGE LINES)	
LT. STA. 1204+50 TO LT. STA. 1212+50	800
RT. STA. 1204+50 TO RT. STA. 1212+50	800
TOTAL =	1800

ITEM NO. 78200410 GUARDRAIL MARKERS, TYPE A

(BASED ON SPACING 80' - MIN. 4)

LOCATION	MONO-DIRECTIONAL SILVER EACH
LT. STA. 1207+71.15	1
RT. STA. 1207+94.85	1
LT. STA. 1208+51.15	1
RT. STA. 1209+54.85	1
LT. STA. 1210+11.15	1
RT. STA. 1210+34.85	1
TOTAL =	6

ITEM NO. 78200530 BARRIER WALL MARKERS, TYPE C

LOCATION	EACH
STRUCTURE NO. 057-0242 (1 EACH SIDE) (MONO-DIRECTIONAL SILVER)	
RT. STA. 1208+74.85	1
LT. STA. 1209+31.15	1
TOTAL =	2

ITEM NO. 78201000 TERMINAL MARKER-DIRECT APPLIED

LOCATION		EACH
STA. 1207+44.85	RT 17'	1
STA. 1207+69.85	LT 17'	1
STA. 1210+36.15	RT 17'	1
STA. 1210+61.15	LT 17'	1
TOTAL =		4

ITEM NO. 78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
(BASED ON 1 MARKER EVERY 80')	
℄ STA. 1204+50 TO ℄ STA. 1212+50	11
TOTAL =	11

ITEM NO. Z0022800 FENCE REMOVAL

LOCATION	FOOT
RT. STA. 1207+98 TO RT. STA. 1208+71	73
LT. STA. 1208+79 TO LT. STA. 1208+79	23
LT. STA. 1209+31 TO LT. STA. 1210+36	105
LT. STA. 1210+36 TO LT. STA. 1210+36	6
RT. STA. 1209+31 TO RT. STA. 1211+00	169
TOTAL =	376

ITEM NO. Z0037300 PAVEMENT GROOVING

LOCATION	SQ. YD.
STA. 1208+33 TO STA. 1208+63	93
STA. 1209+43 TO STA. 1209+73	93
TOTAL =	186

ITEM NO. 66500105 WOVEN WIRE FENCE, 4'

LOCATION	FOOT
RT. STA. 1207+98 TO RT. STA. 1208+63	65
RT. STA. 1208+63 TO RT. STA. 1208+63	14
LT. STA. 1208+63 TO LT. STA. 1208+78	20
LT. STA. 1209+43 TO LT. STA. 1209+53	17
LT. STA. 1209+53 TO LT. STA. 1210+36	83
RT. STA. 1209+43 TO RT. STA. 1209+43	14
RT. STA. 1209+43 TO RT. STA. 1211+00	127
TOTAL =	370

ITEM NO. 48203100 HOT-MIX ASPHALT SHOULDERS

BASED ON 8" THICKNESS

LOCATION	TON
LT. AND RT. STA. 1204+50 TO STA. 1208+63	110
LT. AND RT. STA. 1209+43 TO STA. 1212+50	100
TOTAL =	210

ITEM NO. 40603080 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50

VARIABLE THICKNESS SEE TABLES ON TYPICAL SECTIONS

LOCATION	TON
STA. 1205+50.00 TO STA. 1208+27	412
STA. 1209+79 TO STA. 1211+38.40	159
TOTAL =	571

ITEM NO. 40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

BASED ON 1 1/2" THICKNESS

LOCATION	TON
STA. 1204+50 TO STA. 1208+27	85
STA. 1209+79 TO STA. 1212+50	61
TOTAL =	146

SHEET 2 OF 2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY