

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	3B-1	PIKE	51	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

54201480

**PIPE CULVERTS, TYPE 2, CORRUGATED STEEL
OR ALUMINUM CULVERT PIPE 15"**

UPSTREAM STATION	UPSTREAM OFFSET	DOWNSTREAM STATION	DOWNSTREAM OFFSET	LENGTH (FEET)	TYPE	SIZE (IN)
783+59	59.06 RT	784+32	67.21' RT	73.0	2	15
787+04	46.60' LT	787+51.77	43.35' LT	48.0	2	15
788+95.80	29.63' LT	789+37.08	29.63' LT	41.0	2	15
790+17.21	29.63' LT	790+57.02	29.63' LT	40.0	2	15
791+71.25	29.63' LT	792+08.62	29.63' LT	37.0	2	15
				TOTAL LENGTH:	239'	

EARTHWORK AND SEEDING SCHEDULE

STA.	TO STA.	EARTH EXCAVATION CU. YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU. YD	EMBANKMENT CU. YD	FURNISHED EXCAVATION OR WASTE (-) CU. YD	SEEDING CLASS 2 ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	AGRICULTURAL GROUND LIME TON	MULCH METHOD 2 ACRE	
IL ROUTE 9 / 96	780+05	792+00	2,040	1,530	2,005	475	1.4	135	135	135	3	1.5
JIMTOWN RD.	10+56.59	11+50	255	190	80	-110	0.1					
TOTAL:			2,295	1,720	2,085	365	1.5	135	135	135	3	1.5

54201495

**PIPE CULVERTS, TYPE 2, CORRUGATED STEEL
OR ALUMINUM CULVERT PIPE 30"**

UPSTREAM STATION	UPSTREAM OFFSET	DOWNSTREAM STATION	DOWNSTREAM OFFSET	LENGTH (FEET)	TYPE	SIZE (IN)
782+10	33.26' LT	782+95	42.45' LT	85.0	2	30
10+48.7	45.00' LT	10+66.8	45.00' RT	90.0	2	30
				TOTAL LENGTH:	175'	

28001000

AGGREGATE (EROSION CONTROL) SCHEDULE

STATION	OFFSET
783+55	58.54' LT
783+09	59.72' RT
784+63	69.64' RT
785+09	60.98' RT
792+80	28.18' LT
TOTAL : 150 TON	

28000500

INLET & PIPE PROTECTION SCHEDULE

STATION	OFFSET	EACH
782+03	32.07' LT	1
783+55	58.73' RT	1
783+63	61.95' LT	1
787+00	46.42' LT	1
788+92	29.37' LT	1
790+14	29.62' LT	1
791+67	29.35' LT	1
TOTAL : 7		

63200310

GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH
784+00 RT		785+31.66 RT	130'
783+18.31 LT		10+83.14 LT (JIMTOWN RD)	148'
10+80.35 LT (JIMTOWN RD)		785+36.77	149'
			TOTAL LENGTH: 427'

The Upchurch Group
HILLSIDE, IL. (708) 449-2321
MATTOON, IL. (217) 235-3177

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL 96 OVER JIMTOWN BRANCH
FAP 304 SECTION 3B-1
PIKE COUNTY

SCALE: DATE: \$DATE DRAWN BY: SJF CHECKED BY: MJS