

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
751	101B-2	PIKE	48	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NUMBER	SUMMARY OF QUANTITIES PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	I000 CONSTR. CODE	X071-2A CONSTR. CODE
			80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 20% STATE	IL 106 BRIDGE SN 075-0507 80% FEDERAL 20% STATE
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36	36	-
20200100	EARTH EXCAVATION	CU YD	2750	2750	-
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	128	-	128
25000200	SEEDING, CLASS 2	ACRE	1.1	1.1	-
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	99	99	-
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	99	99	-
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	99	99	-
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.2	2.2	-
25100115	MULCH, METHOD 2	ACRE	1.1	1.1	-
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250	-
28000400	PERIMETER EROSION BARRIER	FOOT	500	500	-
28001000	AGGREGATE EROSION CONTROL	TON	25	25	-
28100109	STONE RIPRAP, CLASS A5	SQ YD	2249	1173	1076
28200200	FILTER FABRIC	SQ YD	2249	1173	1076
35800100	PREPARATION OF BASE	SQ YD	2500	2500	-
35800200	AGGREGATE BASE REPAIR	TON	50	50	-
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	105	105	-
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	30	30	-
40300600	SEAL COAT AGGREGATE	TON	215	215	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2	-
40600300	AGGREGATE (PRIME COAT)	TON	10	10	-
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	67	67	-

PLOT DATE : Aug-15-2007 01:35:52PM  
 PLOT SCALE : 1/8"=1'-0"  
 USER NAME : boughlin

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE  
HORIZ. DRAWN BY  
CHECKED BY