

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
751	101B-2	PIKE	48	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	1000 CONSTR. CODE	X071-2A CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION		80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 20% STATE	IL 106 BRIDGE SN 075-0507 80% FEDERAL 20% STATE
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	160	160	-
40603080	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	417	417	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	146	146	-
42001165	BRIDGE APPROACH PAVEMENT	SO YD	288	288	-
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	48	48	-
44000100	PAVEMENT REMOVAL	SO YD	269	269	-
44004250	PAVED SHOULDER REMOVAL	SO YD	250	250	-
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SO YD	30	30	-
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SO YD	25	25	-
48101200	AGGREGATE SHOULDERS, TYPE B	TON	112	112	-
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	408	408	-
48203100	HOT-MIX ASPHALT SHOULDERS	TON	47	47	-
50100100	REMOVAL OF EXISTING STRUCTURE	EACH	1	-	1
50105220	PIPE CULVERT REMOVAL	FOOT	48	48	-
50200100	STRUCTURE EXCAVATION	CU YD	172	-	172
50300100	FLOOR DRAINS	EACH	8	-	8
50300225	CONCRETE STRUCTURES	CU YD	33	-	33
50300255	CONCRETE SUPERSTRUCTURES	CU YD	115.8	-	115.8
50300260	BRIDGE DECK GROOVING	SO YD	552	261	291
50300300	PROTECTIVE COAT	SO YD	372	-	372
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	-	1
50500505	STUD SHEAR CONNECTORS	EACH	1116	-	1116

PLOT DATE : Aug-18-2007 08:35:45 PM
 PLOT SCALE : 1/8" = 1'-0"
 USER NAME : baughn1

REVISIONS	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY

Rev.