

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|----------|------------------|--------------|-----------|
| 751 | 101B-2 | PIKE | 48 | 9 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

| GUARDRAIL SCHEDULE | | | | | | |
|--------------------------------------|-----------------------------|----------------------------------|------------|-----------|-----------------------------|----------------------|
| LOCATION | TBT T-1 SPL (TANGENT) | TERMINAL MARKER DIR. APPL. | TBT T-6 | SPBGR T-A | GUARDRAIL MARKERS T-A | GUARDRAIL REMOVAL |
| | EACH | EACH | EACH | FOOT | EACH | FOOT |
| NW QUADRANT | | | | | | 110.0 |
| RT STA 378+88.90 TO RT STA 379+38.90 | 1.0 | 1.0 | | | 3.0 | |
| RT STA 379+38.90 TO RT STA 380+38.90 | | | | 100.0 | | |
| RT STA 380+38.90 TO RT STA 380+84.50 | | | 1.0 | | | |
| SW QUADRANT | | | | | | 110.0 |
| LT STA 377+76.40 TO LT STA 378+26.40 | 1.0 | 1.0 | | | 4.0 | |
| LT STA 378+26.40 TO LT STA 380+38.90 | | | | 212.5 | | |
| LT STA 380+38.90 TO LT STA 380+84.50 | | | 1.0 | | | |
| NE QUADRANT | | | | | | 110.0 |
| RT STA 381+15.50 TO RT STA 381+61.10 | | | 1.0 | | 4.0 | |
| RT STA 381+61.10 TO RT STA 383+73.60 | | | | 212.5 | | |
| RT STA 383+73.60 TO RT STA 384+23.60 | 1.0 | 1.0 | | | | |
| SE QUADRANT | | | | | | 110.0 |
| LT STA 381+15.50 TO LT STA 381+61.10 | | | 1.0 | | 3.0 | |
| LT STA 381+61.10 TO LT STA 382+61.10 | | | | 100.0 | | |
| LT STA 382+61.10 TO LT STA 383+11.10 | 1.0 | 1.0 | | | | |
| TOTAL = | 4.0 | 4.0 | 4.0 | 625.0 | 14.0 | 440.0 |

PLOT DATE = Aug-15-2007 01:40:02PM
 FILE NAME = c:\p\projects\6554884\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY