## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO. 2
F.A.P. 751	101B-2	PIKE		48	27	14 SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-			

Contract #72928

## GENERAL NOTES

Fasteners shall be AASHTO M164 Type 3 Bolts. Bolts  $^3_4$  in.  $\phi$ , holes  $^{15}_{16}$  in.  $\phi$ , unless otherwise noted.

Calculated weight of Structural Steel = 76720 lbs.

All structural steel shall be AASHTO M 270 Grade 50W.

No field welding is permitted except as specified in the contract documents.

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60 (IL Modified). See Special Provisions


Reinforcement bars designated (E) shall be epoxy coated.

Structural steel shall only be painted for a distance equal to the depth of embedment into the concrete cap plus 3 inches. Those areas shall be primed in the shop with a Department approved zinc rich primer. No field painting shall be required. All structural steel shall be cleaned as specified in the special provision for "Surface Preparation and Painting Requirements for Weathering Steel".


Layout of slope protection system may be varied in the field to suit ground conditions as directed by the Engineer.

The Contractor shall drive test piles to 110% of the nominal required bearing specified in permanent locations at substructures specified or approved by the Engineer before ordering the remainder of piles.

Excavation behind existing abutment walls shall be performed to balance front and back soil pressure before removing the existing superstructure.



SECTION A-A



## SECTION THRU INTEGRAL ABUTMENT

\* Included in the cost of Pipe Underdrains for Structures, 4".

## Note

All drainage system components shall extend to 2'-0" from the end of each wingwall except an outlet pipe shall extend until intersecting with the side slopes. The pipes shall drain into concrete headwalls. (See Article 601.05 of the Standard Specifications and Highway Standard 601101).

GENERAL DATA

F.A.P. RT. 751 SEC. 101B-2

PIKE COUNTY

STATION 381+00.00

STRUCTURE NO. 075-0507

DESIGNED Nicholas R. Barnett
CHECKED Phillip R. Litchfield
DRAWN Greg D. Farmer

CHECKED NRB/PRL

