

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	139(B-1)	SANGAMON	57	3
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				I000	X080-2A
X0321100	GEOTEXTILE RETAINING WALL	SQ FT	212		212
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	605		605
X0324118	GRANULAR CULVERT BACKFILL	CU YD	750	750	
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1	
XX005519	STONE DUMPED RIPRAP, CLASS A4 (SPECIAL)	TON	618		618
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	1		1
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	374	374	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	252	252	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE: 8/15/07
DRAWN BY JCW
CHECKED BY JRB