

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
735	*	MACOUPIN	4	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 6RS-4; 7RS-7				

Application Rates

Bituminous Materials(Prime Coat)      0.00038 Tons / Sq Yd (0.10 Gal/ Sq Yd)  
 Aggregate Materials (Prime Coat)      0.002 Tons / Sq Yd

<u>Station Range</u>			<u>Width</u>	<u>Length</u>	<u>Area</u>	<u>CAPE Seal</u>	<u>Aggregate</u>	<u>Bituminous</u>	<u>Raised</u>	<u>Raised</u>
			(FT)	(FT)	(SY)	(SY)	(Prime)	(Prime)	Reflective Markers	Reflective Markers
							(TONS)	(TONS)	Removal	Installation
									(EACH)	(EACH)
72+34.	TO	171+86.7	20	9,953	22,117	22,117	44.2	8.4	124	124
173+60.	TO	252+91.	20	7,931	17,624	17,624	35.2	6.7	99	99
399+75.	TO	558+58.	20	15,883	35,296	35,296	70.6	13.4	199	199
<i>Totals</i>				<i>33,767</i>	<i>75,037</i>	<i>75,037</i>	<i>150</i>	<i>28.5</i>	<i>422</i>	<i>422</i>
				<i>6.395 mi</i>						

Paint Pavement Marking Line, 5"

Location	Length	Edge Line	Center Dash	Center Solid
	(FT)	(FT)	(FT)	(FT)
Passing Zone	13,507	27,013	3,377	0
No Passing - One Way	8,442	16,883	2,110	8,442
No Passing Zones	11,818	23,637	0	23,637
sub-Totals		67,533	5,487	32,078

*Total 105,099*

Notes:

The Fine Aggregate used with the A-1 treatment for the CAPE seal shall be CA-16.  
 For Plan Circulation, assume 35% of length will be No-Passing zones, 25% No-Passing one way.

PLOT DATE = Aug 13, 2007 08:45:09A  
 FILE NAME = c:\p1\proj\735\73503\73503.dwg  
 PLOT SCALE = 100.0000 / 1.00  
 USER NAME = laughlinr1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP 735  
 SECTION 6RS-4; 7RS-7  
 MACOUPIN COUNTY  
 SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE