

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
34	*	**	13	4

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- * D-6 SHLDR RUMBLE STRIPS 2008
- ** MENARD, SANGAMON COUNTY

HOT MIX ASPHALT SHOULDER SCHEDULE & RUMBLE STRIPS

LOCATION (STA TO STA)	EXISTING HMA SHLD WIDTH	LENGTH	EXCAVATING AND GRADING EXISTING SHOULDERS <i>20200600</i>	HMA SHOULDERS 8" <i>48203029</i>	AGG SHOULDERS TY - B <i>48101200</i>	SHOULDER RUMBLE STRIPS <i>64200105</i>	PAINT PAVEMENT MARKING LINE 5" <i>78001120</i>
	FOOT	FOOT	UNIT	SQ YD	TON	FOOT	FOOT
IL 97 - PART "A" MENARD COUNTY							
LT 243+68.15 (AH) TO LT 337+50	8.0	9,381.9	0.0	0.0	0	9,381.9	
RT 243+68.15 (AH) TO RT 337+36	8.0	9,367.9	0.0	0.0	0	9,367.9	
308+55 (GUARDRAIL BOX CULVERT)							
300+07 (GUARDRAIL BOX CULVERT)							
IL 97 - PART "B" MENARD COUNTY							
LT 14+33.15 (AH) TO LT 88+08	1.0	7,374.9	73.7	2,458.3	344.2	7,374.9	7,374.9
LT 88+08 TO LT 97+36	4.0	928.0	0.0	0.0	0	928.0	
LT 97+36 TO LT 99+98.76 (BK)	1.0	262.8	2.6	87.6	12.3	262.8	262.8
LT 100+00.00 (AH) TO LT 104+05	1.0	405.0	4.1	135.0	18.9	405.0	405.0
LT 104+05 TO LT 105+41 (BRIDGE OMISSION)		136.0					
LT 105+41 TO LT 106+08	1.0	67.0	0.7	22.3	3.1	67.0	67.0
LT 106+08 TO LT 110+00.00 (BK)	8.0	392.0	0.0	0.0	0	392.0	
LT 110+00.21 (AH) TO LT 113+62	8.0	361.8	0.0	0.0	0	361.8	
LT 113+62 TO LT 114+00	8.0	38.0	0.0	0.0	0	38.0	
LT 114+00 TO LT 225+96.63 (BK)	1.0	11,196.6	112.0	3,732.2	522.5	11,196.6	11,196.6
LT 226+00.77 TO LT 234+28.00	1.0	827.2	8.3	275.7	38.6	827.2	827.2
RT 14+33.15 (AH) TO RT 87+70	1.0	7,336.9	73.4	2,445.6	342.4	7,336.9	7,336.9
RT 87+70 TO RT 97+10	4.0	940.0	0.0	0.0	0	940.0	
RT 97+10 TO RT 99+98.76 (BK)	1.0	288.8	2.9	96.3	13.5	288.8	288.8
RT 100+00.00 (AH) TO RT 104+05	1.0	405.0	4.1	135.0	18.9	405.0	405.0
RT 104+05 TO RT 105+41 (BRIDGE OMISSION)		136.0					
RT 105+41 TO RT 107+08	1.0	167.0	1.7	55.7	7.8	167.0	167.0
RT 107+08 TO RT 110+00.00 (BK)	8.0	292.0	0.0	0.0	0	292.0	
RT 110+00.21 (AH) TO RT 113+62	8.0	361.8	0.0	0.0	0	361.8	
RT 113+62 TO RT 114+00	8.0	38.0	0.0	0.0	0	38.0	
RT 114+00 TO RT 225+96.63 (BK)	1.0	11,196.6	112.0	3,732.2	522.5	11,196.6	11,196.6
RT 226+00.77 TO RT 234+28	1.0	827.2	8.3	275.7	38.6	827.2	827.2

PLOT DATE = Aug-15-2007 10:02:10AM
 FILE NAME = c:\p\projects\610597\ahsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE
 FAP 34 (IL 97)
 SECTION D-6 SHLDR
 RUMBLE STRIPS 2008
 MENARD, SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____