

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
34	*	**	13	5

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- * D-6 SHLDR RUMBLE STRIPS 2008
- ** MENARD, SANGAMON COUNTY

HOT MIX ASPHALT SHOULDER SCHEDULE & RUMBLE STRIPS							
LOCATION (STA TO STA)	EXISTING	LENGTH	EXCAVATING	HMA	AGG	SHOULDER	PAINT
	HMA SHLD		AND GRADING	SHOULDERS	SHOULDERS	RUMBLE	PAVEMENT
	WIDTH		EXISTING	8"	TY - B	STRIPS	MARKING
			SHOULDERS				LINE 5"
			20200600	48203029	48101200	64200105	78001120
	FOOT	FOOT	UNIT	SQ YD	TON	FOOT	FOOT
IL 97 - PART "B" SANGAMON COUNTY							
LT 234+28 TO LT 291+64	1.0	5,736.0	57.4	1,912.0	267.7	5,672.0	5,736.0
LT 291+64 TO LT 300+68	0.0	904.0	0.0	0.0	0	0.0	
LT 300+68 TO LT 314+35	1.0	1,367.0	13.7	455.7	63.8	635.0	1,367.0
LT 314+35 TO LT 326+34	8.0	1,199.0	0.0	0.0	0	1,199.0	
LT 326+34 TO LT 331+23.59	1.0	489.6	4.9	163.2	22.8	489.6	489.6
LT 331+23.59 TO LT 332+31.76 (BRIDGE OMISSION)		108.2					
LT 332+31.76 TO LT 337+89	1.0	557.2	5.6	185.7	26.0	557.2	557.2
LT 337+89 TO LT 347+50	8.0	961.0	0.0	0.0	0	961.0	
LT 347+50 TO LT 444+50	1.0	9,700.0	97.0	3,233.3	452.7	9,700.0	9,700.0
LT 444+50 TO LT 451+68.21 (BK)	8.0	718.2	0.0	0.0	0	718.2	
LT 452+00.00 (AH) TO LT 455+00	8.0	300.0	0.0	0.0	0	300.0	
LT 455+00 TO LT 456+47	8.0	147.0	0.0	0.0	0	147.0	
LT 456+47 TO LT 457+41 (BRIDGE OMISSION)		94.0					
LT 457+41 TO LT 462+00	8.0	459.0	0.0	0.0	0	459.0	
LT 462+00 TO LT 465+50	8.0	350.0	0.0	0.0	0	350.0	
LT 465+50 TO LT 498+50	8.0	3,300.0	0.0	0.0	0	3,300.0	
RT 234+28 TO RT 291+00	1.0	5,736.0	57.4	1,912.0	267.7	5,736.0	5,736.0
RT 291+00 TO RT 304+00	0.0	904.0	0.0	0.0	0	0.0	
RT 304+00 TO RT 313+30	1.0	1,367.0	13.7	455.7	63.8	530.0	1,367.0
RT 313+30 TO RT 320+14	8.0	1,199.0	0.0	0.0	0	1,199.0	
RT 320+14 TO RT 330+55	1.0	489.6	4.9	163.2	22.8	489.6	489.6
RT 330+55 TO RT 331+23.59	4.0	1,199.0	0.0	0.0	0	1,199.0	
RT 331+23.59 TO RT 332+31.76 (BRIDGE OMISSION)		108.2					
RT 332+31.76 TO RT 333+00	4.0	1,199.0	0.0	0.0	0	1,199.0	
RT 333+00 TO RT 337+89	1.0	557.2	5.6	185.7	26.0	557.2	557.2
RT 337+89 TO RT 348+25	8.0	961.0	0.0	0.0	0	961.0	
RT 348+25 TO RT 444+50	1.0	9,700.0	97.0	3,233.3	452.7	9,700.0	9,700.0
RT 444+50 TO RT 450+00	8.0	1,050.0	0.0	0.0	0.0	1,050.0	
RT 450+00 TO RT 451+68.21 (BK)	8.0	168.2	0.0	0.0	0.0	168.2	
RT 452+00.00 (AH) TO RT 456+47	8.0	447.0	0.0	0.0	0.0	447.0	
RT 456+47 TO RT 457+41 (BRIDGE OMISSION)		94.0					
RT 457+41 TO RT 459+50	8.0	459.0	0.0	0.0	0.0	459.0	
RT 459+50 TO RT 467+50	8.0	350.0	0.0	0.0	0.0	350.0	
RT 467+50 TO RT 498+50	8.0	3,300.0	0.0	0.0	0.0	3,300.0	
ENTRANCES					-46.7	-1,000.0	-500.0
TOTAL =			760.5	25,351.5	3,502.5	113,289.3	75,554.6

NOTE:

TOWN OF SALISBURY
OMISSION OF RUMBLE STRIP
290+00 TO 308+00

118406.640 FEET
x 0.5
59203.320 FEET
11.213 MILES

PLOT DATE = Aug-15-2007 10:02:11AM
FILE NAME = c:\p\projects\0610507\ahsch.dgn
PLOT SCALE = 1/8"=1'-0" / IN.
USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE
FAP 34 (IL 97)
SECTION D-6 SHLDR
RUMBLE STRIPS 2008
MENARD, SANGAMON COUNTY
SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE