

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	44	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* D7 SAFETY 2008-2

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
				EFFINGHAM COUNTY			COLES COUNTY	
				I-57 URBAN 4 LANE FED 90% STATE 10%	I-57 RURAL 4 LANE FED 90% STATE 10%	I-57 RURAL 4 LANE FED 90% STATE 10%	I-57 URBAN 4 LANE FED 90% STATE 10%	I-57 RURAL 4 LANE FED 90% STATE 10%
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-3J	SFTY-3J	SFTY-3J	SFTY-3J	SFTY-3J
20200100	EARTH EXCAVATION	CU YD	102			57		45
20400800	FURNISHED EXCAVATION	CU YD	1764			1661		103
25000200	SEEDING, CLASS 2	ACRE	2.1			1.6		0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	189			140.4		48.6
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	189			140.4		48.6
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	189			140.4		48.6
25100115	MULCH, METHOD 2	ACRE	2.1			1.6		0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	210			156		54
28000500	INLET AND PIPE PROTECTION	EACH	1			1		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	63	49.6	13.4			
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	395			395		
54205059	PIPE CULVERTS, SPECIAL 24"	FOOT	12			12		
54246405	INLET BOX, STANDARD 542531	EACH	3			3		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	174.5			174.5		
60239400	INLETS, TYPE A, SPECIAL, TYPE 8 GRATE	EACH	1			1		
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	6550	5650	600		300	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	30	25	3		2	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	29	24	3		2	
63200310	GUARDRAIL REMOVAL	FOOT	2024.5	2024.5				
63400105	GUARD POSTS	EACH	40			30		10
67100100	MOBILIZATION	L SUM	1	0.2	0.2	0.2	0.2	0.2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1			0.75		0.25
78200410	GUARDRAIL MARKERS, TYPE A	EACH	102	87	9		6	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	29	24	3		2	
X0301894	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAIN	EACH	2			2		
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	5			5		
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8			6		2

PLOT DATE = 8/1/2007
 FILE NAME = d:\projects\74249\summary.dgn
 USER NAME = sbrtzw

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
 DATE

DRAWN BY
 CHECKED BY

Rev. 10-29-07

Rev.