

SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	95-(5,6)RS-1 WASHINGTON	83	5
CONTRACT NO.: 76A39			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	X231-2A SN 095-0060	X131-2A SN 095-0061	X131-2A SN 095-0062	X231-2A SN 095-0063	X231-2A SN 095-0064	Y002-1C 100% STATE
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	184	184						
* 73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	32	32						
* 73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	20	20						
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	10	10						
* 73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	172500	172500						
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2180	2180						
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	20642	20642						
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3005	3005						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2153	2153						
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20	20						
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	65	65						
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	32	32						
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	32	32						
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1361	1361						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2123	2123						
X0321468	PLUG EXISTING DECK DRAINS	EACH	8		8					
X0322729	MATERIAL TRANSFER DEVICE	TON	58459	58459						
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	60		60					
X0323491	SLOPE WALL CRACK SEALING	FOOT	434		58	188	188			
⚠ Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	164594	164594						
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH LESS THAN OR EQUAL TO 5 INCHES)	SQ FT	182			14	14	77	77	
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	28130	28130						
Z0010400	CLEANING BRIDGE SEATS	SQ FT	1049			243	243	281.5	281.5	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4						
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			0.5	0.5			
Z0076850	UNSOOUND CONCRETE REMOVAL	SQ YD	35			16	19			

PLOT DATE = 9/15/2007
 FILE NAME = c:\pcc\mcs\and\207\plan\p102267b.dgn
 PLOT SCALE = 49.5893' / IN.
 REFERENCE = #REF#

*SPECIALTY ITEMS

Rev. 10-26-07

Rev.