

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 24	.	JOHNSON WILLIAMSON	35	3

*SECTION 09 BRIDGE PAINTING FY 08-1
CONTRACT NO. 78020

The term "Beam End" is used in this document to indicate all structural steel within 5 feet (measured along the beam) of either side of a deck joint, unless otherwise noted. Beam End locations are shown on the general elevation view of each structure.

Cleaning and painting shall conform to the requirements of special provision "Cleaning And Painting Existing Steel Structures". Near White Metal Blast Cleaning - SSPC - SP10 and Paint System 1 - OZ / E / U shall be used unless otherwise noted.

SSPC - QP1 and SSPC - QP2 Painting Contractor Certifications are required.

The color of the final finish coat shall be Gray, Munsell No. 5B 7/1, except the color of the final finish coat for outside surfaces of fascia beams shall be Interstate Green, Munsell No. 7.5G 4 / 8.

044-0041 & 044-0042

Beam Ends and exterior surfaces of fascia beams, including the bottom of the bottom flange, shall be painted on each structure. See Beam End locations on Sheets 6 and 11 of 35.

Painting of existing new bearings is not required.

Seismic shock absorbers are present at the Beam Ends on Structure 044-0042. The Contractor shall use care to avoid damage or disturbance of these devices.

A minimum of 3 air monitors are required when work is performed at only one bridge.

A minimum of 4 air monitors are required when work is performed at both bridges simultaneously.

044-0049 & 044-0050

Beam Ends and exterior surfaces of fascia beams, including the bottom of the bottom flange, shall be painted on each structure. See Beam End locations on Sheets 16 and 20 of 35.

Painting of existing new bearings is not required.

A minimum of 3 air monitors are required when work is performed at only one bridge.

A minimum of 4 air monitors are required when work is performed at both bridges simultaneously.

100-0059

All structural steel shall be painted.

A minimum of 1 air monitor is required when work is performed at this site.

100-0060

All structural steel shall be painted.