

SUMMARY OF QUANTITIES

Item	Items	Unit	1000-2A QUANTITY	X071-2A QUANTITY	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	320	0	320
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	146	0	146
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	0	100	100
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	68	0	68
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	690	0	690
25000300	SEEDING, CLASS 3	ACRE	0.32	0	0.32
25100630	EROSION CONTROL BLANKET	SQ YD	1020	0	1020
25200200	SUPPLEMENTAL WATERING	UNIT	45	0	45
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.32	0	0.32
28000400	PERIMETER EROSION BARRIER	FOOT	900	0	900
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	0	190	190
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	562	0	562
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	57	0	57
40600300	AGGREGATE (PRIME COAT)	TON	1.5	0	1.5
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	114	0	114
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	49	0	49
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	220	0	220
44000100	PAVEMENT REMOVAL	SQ YD	597	0	597
44000700	APPROACH SLAB REMOVAL	SQ YD	200	0	200
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	230	0	230
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	0	1	1
50200100	STRUCTURE EXCAVATION	CU YD	0	320	320
50300225	CONCRETE STRUCTURES	CU YD	0	183	183
50300255	CONCRETE SUPERSTRUCTURE	CU YD	0	201	201
50300260	BRIDGE DECK GROOVING	SQ YD	0	520	520
50300300	PROTECTIVE COAT	SQ YD	0	710	710
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	0	1	1
50500505	STUD SHEAR CONNECTORS	EACH	0	2595	2595
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	0	57780	57780
63100085	TRAFFIC BARRIER TERMINAL, TYPE L	EACH	4	0	4

Item	Items	Unit	1000-2A QUANTITY	X071-2A QUANTITY	TOTAL QUANTITY
50800515	BAR SPLICERS	EACH	0	64	64
51100100	SLOPE WALL 4 INCH	SQ YD	0	210	210
51201400	FURNISHING STEEL PILES HP10X42	FOOT	0	575	575
51201600	FURNISHING STEEL PILES HP12X63	FOOT	0	535	535
51202305	DRIVING PILES	FOOT	0	1110	1110
51203400	TEST PILE STEEL HP10X42	EACH	0	2	2
51203600	TEST PILE STEEL HP12X63	EACH	0	2	2
51204650	PILE SHOES	EACH	0	20	20
51500100	NAME PLATES	EACH	0	1	1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	0	72	72
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	0	128	128
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	137	0	137
63200310	GUARDRAIL REMOVAL	FOOT	47	0	47
67100100	MOBILIZATION	L SUM	1	0	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	400	0	400
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	305	0	305
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	435	0	435
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	385	0	385
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	0	4	4
X0607107	SILT CURTAIN	FOOT	185	0	185
Z0001040	AGGREGATE SUBGRADE 8"	SQ YD	850	0	850
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0	1
Z0076600	TRAINEES	HOUR	500	0	500
XX066339	FENCE TO BE REMOVED AND REPLACED	FOOT	40	0	40
XX067093	STRAW BALE BARRIER PLAN	FOOT	200	0	200
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 1	EACH	0	1	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 2	EACH	0	1	1

* SPECIALTY ITEM
 Δ Y080

CHRISTOPHER B. BURKE ENGINEERING LTD.
 9575 West Higgins Road, Suite 600
 Rosemont, Illinois 60018
 (847) 823-0500
 CBB
 DATE: _____ BY: _____
 CHECKED: _____
 DATE: _____
 NO. _____
 STRUCTURE NOTATIONS ONLY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**TIMBER EDGE DRIVE
SUMMARY OF QUANTITIES**

SCALE: N.T.S. DRAWN BY: BEH
 DATE: 8/24/2007 CHECKED BY: LMF