

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
--	03-00019-00-BR	DUPAGE	35	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83965

PROFILE
 DATE: _____
 BY: _____
 CHECKED BY: _____
 DATE: _____
 NO. OF MAY CHECKED: _____
 CAD FILE NAME: _____

CHRISTOPHER B. BURKE ENGINEERING LTD.
 9575 West Higgins Road, Suite 600
 Rosemont, Illinois 60018
 (847) 823-0500

PROFILE
 DATE: _____
 BY: _____
 CHECKED BY: _____
 DATE: _____
 NO. OF MAY CHECKED: _____
 CAD FILE NAME: _____

EARTHWORK SCHEDULE

STATION	EARTH EXCAVATION** (CY)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CY)	EMBANKMENT (CY)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)
WEST OF BRIDGE				
101+00.00	0.0	0.0	0.0	0.0
101+50.00	96.8	82.2	6.8	75.5
102+00.00	90.9	77.3	4.3	73.0
102+23.27	33.8	28.7	4.7	24.0
SUBTOTAL	221.5	188.2	15.8	172.5
EAST OF BRIDGE				
104+39.38	0.0	0.0	0.0	0.0
104+50.00	8.4	7.1	15.7	-8.6
105+00.00	87.9	74.7	44.2	30.5
SUBTOTAL	96.2	81.8	59.9	21.9
TOTAL	317.7	270.1	75.6	194.4

** WILL BE PAID FOR AS EARTH EXCAVATION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

EARTHWORK SCHEDULE

SCALE: N.T.S. DRAWN BY: BEH

DATE: 8/24/2007 CHECKED BY: LMF