



MATCHLINE STA. 19+00

MATCHLINE STA. 19+00

**LEGEND**

- ① EPOXY PAVEMENT MARKING LINE 4" (SINGLE WHITE)
- ② EPOXY PAVEMENT MARKING LINE 4" (DOUBLE YELLOW)
- ③ EPOXY PAVEMENT MARKING 6" (SINGLE WHITE)
- ④ EPOXY PAVEMENT MARKING LINE (DOTTED WHITE)
- ⑤ EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS SEE DISTRICT 1 TYPICAL PAVEMENT MARKINGS FOR SPACING
- ⑥ EPOXY PAVEMENT MARKING LINE 12" (SINGLE YELLOW)

LOCATION	EPOXY PAVEMENT MARKING						TEMPORARY PAINT PAVEMENT MARKING					
	LINE 4" SOLID WHITE	LINE 4" SOLID YELLOW	LINE 6" SOLID WHITE	LINE 6" DOTTED WHITE	LINE 12" SOLID YELLOW	LETTERS AND SYMBOLS	LINE 4" SOLID WHITE	LINE 4" SOLID YELLOW	LINE 6" SOLID WHITE	LINE 6" DOTTED WHITE	LINE 12" SOLID YELLOW	LETTERS AND SYMBOLS
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
RT. STA. 15+50 TO STA. 23+50	800						1600					
LT. STA. 15+50 TO STA. 23+50	800						1600					
CL. STA. 15+50 TO STA. 23+50		3200						6400				
8' LT. STA. 15+50 TO STA. 12+11			161						298			
8' LT. STA. 17+11 TO STA. 18+79.10				42					90			
20' LT. STA. 15+50 TO STA. 15+99.10			49						98			
20' LT. STA. 15+99.10 TO STA. 18+29.10				58					115			
8' RT. STA. 20+79.50 TO STA. 23+09.50				58					115			
8' RT. STA. 23+09.50 TO STA. 23+50			41					82				
MEDIAN DIAGONALS					135					270		
STA. 15+50 TO STA. 23+50						109						218
SUBTOTAL	1600	3200	251	158	135	109	3200	6400	478	320	270	218
TOTAL		4800		409	135	109		9600		798	270	218

NOTE: TEMPORARY PAINT PAVEMENT MARKINGS TO BE USED DURING RESURFACING SHALL BE THE SAME DESIGN AS THE FINAL EPOXY PAINT PAVEMENT MARKINGS.

**HAMPTON, LENZINI & RENWICK, INC.**  
 CIVIL & STRUCTURAL ENGINEERS  
 LAND SURVEYORS

**HLR**

3085 STEVENSON DRIVE, SUITE 201  
 SPRINGFIELD, ILLINOIS 62703  
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-05-0050-1    DATE: 08/29/07  
 DESIGNED: L.F.S.    CHECKED: S.W.M.    DRAWN: D.T.M.

**FINAL ROADWAY AND PAVEMENT MARKING PLAN**  
 SECTION 01-00268-00-BR  
 F.A.S. 2111 / FABYAN PARKWAY  
 KANE COUNTY