

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5355	04-00167-00-WR	DEKALB	62	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE NO	SLOPE (%)	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 27"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	STORM SEWERS, DUCTILE IRON 8"	BACKFILL (CU YD)	COMMENTS
200	0.20						42.67							0	
201	4.00						9.00							6	
202	0.30								3.50					0	
203	0.30	45.79												6	
204	0.20										95.00			82	
205	0.40	8.08												1	
206	0.20										69.00			50	
208	0.20		3.71											1	
209	0.50	13.03												2	
210	0.20	45.58												6	
211	0.50	13.03												2	
212	0.30									171.00				117	
213	0.50								5.50					2	
214	0.30								3.50					0	
215	0.30	45.79												6	
216	0.35			95.50										28	
217	0.50								4.00					1	
218	0.50	45.79												6	
219	0.30			107.88										37	
220	0.40	53.55												7	
221	0.99	102.80												14	
222	1.54		50.00											7	
300	0.20											23.51		0	
301	0.20							6.00						4	
302	5.00								5.50					2	
303	0.50	45.79												7	
304	0.20										95.00			99	
305	5.00								5.50					1	
306	0.50	45.79												6	
307	0.20										95.02			85	
308	0.40	3.50												1	
309	0.20							85.00						63	
310	0.40			3.71										1	
311	10.00								7.05					1	
312	0.40			45.58										12	
313	0.50	6.50												2	
314	6.50												8.00	0	
315	0.20							105.00						75	
316	0.30	2.50												0	
317	0.50	45.79												6	
318	0.20							46.29						33	
319	0.20							76.13						23	
320	0.50			15.77										11	
321	0.20					13.75								4	
322	0.50			45.95										11	
323	0.75												7.89	0	
324	0.20				95.31									0	
325	5.00	5.00												1	
326	0.50	45.79												6	
327	2.62	145.51												0	
328	5.00	4.00												1	
329	0.50	46.00												9	
330	3.30	166.00												0	
331	5.00	4.00												1	
332	0.50	45.79												6	
333	2.64	146.00												0	
334	0.50	4.00												1	
335	0.50	45.79												6	
336	0.75												6.00	0	
TOTAL		1181.19	53.71	314.39	95.31	13.75	51.67	318.42	34.55	171.00	164.00	213.53	21.89	858	

PLOT DATE = 8/16/2007  
 FILE NAME = I:\Dekalb\157283-BethanyRd\Cvt1\Drawn\1\016810.dgn  
 PLOT SCALE = N.T.S.  
 USER NAME = \_USER\_



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 BETHANY ROAD WIDENING  
 FAIRWAY OAKS DRIVE TO RESOURCE PARKWAY  
 CITY OF DEKALB  
 DRAINAGE SCHEDULE  
 BETHANY ROAD

SCALE: N.T.S. DRAWN BY KMA  
 DATE 8/17/07 CHECKED BY BP