

SUMMARY OF QUANTITIES

(101BY)BR(28-BR)
** WARREN

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	**	97	5
STA.		TO STA.	
FED. ROAD DIST. NO. 4		ALTERN.	FED. AID PROJECT

ACBRF ACBHF ACBRF ACBHF

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		SN 094-0049 X081-2A	SN 094-0002 X071-2A	TOM'S ROADWAY I000	MID HEND ROWY I000	TRAINING Y080
28100830	STONE DUMPED RIPRAP, CLASS B4	TON	147				147	
28200200	FILTER FABRIC	SQ YD	4023	817	1384	222	1600	
35600708	HOT - MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	860			302	558	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	161			52	109	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2			1	1	
40600300	AGGREGATE (PRIME COAT)	TON	10			5	5	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	564			221	343	
40600990	TEMPORARY RAMP	SQ YD	226			90	136	
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19 .0, N50	TON	193				193	
40603335	HOT MIX - ASPHALT SURFACE COURSE, MIX "D ", N50	TON	540			275	265	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	450			225	225	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	86			43	43	
44000100	PAVEMENT REMOVAL	SQ YD	656			416	240	
44000198	HOT - MIX ASPHALT SURFACE REMOVAL, VARIA BLE DEPTH	SQ YD	3487			2200	1287	
44000400	GUTTER REMOVAL	FOOT	108			108		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	94				94	
44002500	GUTTER OUTLET REMOVAL	EACH	2			2		