**CONTRACT NO. 88798** F.A.P. SECTION COUNTY TOTAL SHEET NO. 310 (28BR)I WARREN 97 22 STA. 824+00 TO STA. 833+50 FED. ROAD DIST. NO. ILLINOIS US 67 Z STONE RIPRAP, CLASS, A5 STONE DUMPED RIPRAP, CLASS B4 -STONE RIPRAP. CLASS, 84 EXISTING R.O.W. CONST LIMITS EXISTING R.O.W. 1835+00 (c) EXISTING R.O.W. EXISTING R.O.W. - RESHAPE CHANNEL BANKS TO A 2:1 SLOPE EROSION CONTROL PLAN STONE RIPRAP, CLASS B4 \*\* - TRANSITION TO EXISTING CHANNEL TEMPORARY EROSION CONTROL STONE RIPRAP. TEMPORARY DITCH CHECK PERIMETER EROSION BARRIER SEDIMENT BASIN PERMANENT EROSION CONTROL CLASS A4 RIPRAP PRIOR TO BEGINNING EARTHWORK OR STRUCTURE REMOVAL, PERIMETER EROSION BARRIER SHALL BE PLACED AS GIVEN IN ACCORDANCE WITH THE TYPICAL APPLICATION OF SILT FILTER FENCE DETAIL AND SECTION 280 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND AS DIRECTED BY THE RESIDENT ENGINEER. TEMPORARY DITCH CHECKS AND INLET AND PIPE PROTECTION SHALL BE PLACED AS GIVEN IMMEDIATELY UPON DISTURBANCE OF EXISTING SLOPES IN ACCORDANCE WITH THE EROSION CONTROL SPECIAL PROVISION AND SECTION 280 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND AS DIRECTED BY THE RESIDENT ENGINEER. PERMANENT CLASS A4 RIPRAP AND SEEDING, CLASS 3 SHALL BE PLACED IMMEDIATELY AFTER FINAL GRADING FOR PROPOSED DITCHES IN ACCORDANCE WITH SECTIONS 250, 251, 281, AND 282 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND AS DIRECTED BY THE RESIDENT ENGINEER. ILLINOIS DEPARTMENT OF TRANSPORTATION MIDDLE HENDERSON CREEK SEC (28BR)I SN 094-0002 **EROSION CONTROL PLAN** DRAWN BY: BAD SCALE

CHECKED BY: JLG