

# SUMMARY OF QUANTITIES

P.A. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	1108B/BR, BR-1	McDonough	80	5
STA. 63+00		TO STA. 74+00		

ACBRE ACF

ACBRE ACF

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		FED-ST 80-20 X028-2A 055-2004	FED-ST 80-20 X028-2A 055-2500
60603200	CONCRETE GUTTER TRANSITION (SPECIAL)	FOOT	24		24
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2		2
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	850	850	
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	100	100	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3	
63100169	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (FLARED)	EA	1	1	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	418	418	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	10	10	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	5	3
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	12	6	6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3188	2475	713
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3570	2360	1210
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1190.6	786.6	404
70400100	TEMPORARY CONCRETE BARRIER	FOOT	628	358	270
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	580	310	270
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	4		4
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3188	2475	713
78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SO FT	394	394	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		FED-ST 80-20 X028-2A 055-2004	FED-ST 80-20 X028-2A 055-2500
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3"	FOOT	4	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3"	EACH	4	2	2
Z0054500	ROCK FILL	TON	561	383	178
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1	1	
Z0076600	TRAINEES	HOUR	500	250	250
XX002909	CLASS SI CONCRETE	CU YD	12.4		12.4
X5121800	PERMANENT STEEL SHEET PILING	SO FT	1521	1521	
X0322886	GRATING FOR BOX CULVERT, LOCATION 1	EACH	2	2	
X0712400	TEMPORARY PAVEMENT	SO YD	207.1	207.1	
X0919000	TEMPORARY PAVEMENT REMOVAL	EACH	207.1	207.1	

Y080 (80% FED 20% STATE)

\* SPECIALTY ITEM