

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	10BBIBR, BR-1	MCDONOUGH	80	11
STA63+00		TO STA74+00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

70300520 PAVEMENT MARKING TAPE, TYPE III, 4"

LOCATION	QUANTITY (FOOT)
Sta. 63+52 RT - (Stop bar 24")	72
Stage I - Sta. 64+56 to 70+52 LT, Sta. 64+88 to 69+52 RT	1066
Stage II - Sta. 64+80 to 69+88 LT, Sta. 63+62 to 69+76 RT	1150
Sta. 70+88 LT - (Stop Bar 24")	72
GRAND TOTAL =	2380

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ. FT.)
STATION	
STAGE I	355.3
STAGE II	383.3
STOP BARS	48
TOTAL =	786.6

70400100 TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STA. 65+40 TO 68+98	358
TOTAL =	358

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STA. 65+40 TO 68+98	310
TOTAL =	310

78005110 EPOXY PAVEMENT MARKING LINE - 4"

LOCATION	QUANTITY (FOOT)
Sta. 63+00 to 74+00	2475
GRAND TOTAL =	2475

78200410 GUARDRAIL MARKERS, TYPE A

LOCATION	QUANTITY (EACH)
Rt Sta. 63+00 TO 74+00	7
Lt Sta. 63+00 TO 74+00	7
TOTAL =	14

78201000 TERMINAL MARKERS -DIRECT APPLIED

LOCATION	QUANTITY (EACH)
Rt Sta. 63+00 TO 74+00	2
Lt Sta. 63+00 TO 74+00	2
TOTAL =	4

78300100 PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ. FT.)
LT Edge of Pavement Sta 64+58 to 69+88	177
Centerline Sta 63+52 to 70+86	62
RT Edge of Pavement Sta 64+88 TO 69+52	155
TOTAL =	394

X0322886 GRATING FOR BOX CULVERT, LOCATION 1

LOCATION	QUANTITY (EACH)
LT & RT 73+10	2
TOTAL =	2

X0712400 TEMPORARY PAVEMENT

LOCATION	QUANTITY (SQ YD)
Sta. 64+88 to 69+52	207.1
TOTAL =	207.1

X0919000 TEMPORARY PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ YD)
Sta. 64+88 to 69+52	207.1
TOTAL =	207.1

Z0013798 CONSTRUCTION LAYOUT

LOCATION	QUANTITY (L SUM)
Jobsite	0.5
TOTAL =	0.5

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
Jobsite	2
TOTAL =	2

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
Jobsite	2
TOTAL =	2

Z0054500 ROCK FILL

LOCATION	QUANTITY (TON)
Sta. 66+70 to 67+69	347
Lt & Rt Sta. 73+10	36
TOTAL =	383

EARTHWORK SUMMARY FOR INFORMATION ONLY

PAY ITEM	CU YD	SHRINKAGE .25%	BALANCE
20200100 EARTH EXCAVATION	564	141	423
20300100 CHANNEL EXCAVATION	469	117	352
50200100 STRUCTURE EXCAVATION	914	228	686
SUB-TOTAL			1461
EMBANKMENT	611		+850

Channel Excavation may require a larger shrinkage factor.

PLT DATE = 8/14/2007
 FILE NAME = S:\GEN\WORK\T\ST01PL\US\504003\88799 N Adm\1\qms2.dgn
 PLT SCALE = 1/8"=1'-0"
 USER = jbr

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
 DATE

DRAWN BY
 CHECKED BY