

44000100 PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STATION	
U.S. 136	
142+32.5 TO 142+67.5	93.3
143+43.5 TO 143+80.0	97.3
W. CHERRY STREET	
9+50.0 TO U.S. 136	81.4
E. CHERRY STREET	
U.S. 136 TO 10+52.0	97.9
TOTAL =	369.9

44000400 GUTTER REMOVAL

LOCATION	QUANTITY (FOOT)
STATION	
STA. 143+13.50 TO 144+00.00, RT.	87.4
TOTAL =	87.4

44000600 SIDEWALK REMOVAL

LOCATION	QUANTITY (SQ. FT.)
STATION	
STA. 143+24.6 TO STA. 143+52.5, RT.	70.4
TOTAL =	70.4

44000700 APPROACH SLAB REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STATION	
142+67.5 TO 142+97.5	80
143+13.5 TO 143+43.5	80
TOTAL =	160.0

44000920 BITUMINOUS CONCRETE SHOULDER REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STATION	
STA. 143+13.50 TO 144+00.00, RT. TEMPORARY SHOULDER	45.0
STA. 143+46.19 TO 144+00.00, RT.	18.0
TOTAL =	63.0

48101500 AGGREGATE SHOULDERS, TYPE B 6"

LOCATION	QUANTITY (SQ. YD.)
STATION	
STA. 142+15.27 TO 142+98.65, LT.	29.6
STA. 142+32.50 TO 142+91.82, RT.	27.1
STA. 143+16.69 TO 143+80.00, LT.	33.9
TOTAL =	90.6

48203037 HOT-MIX ASPHALT SHOULDERS 10"

LOCATION	QUANTITY (SQ. YD.)
STATION	
STA. 142+32.50 TO 142+69.61, LT.	12.6
STA. 143+46.19 TO 144+00.00, RT. TEMPORARY SHOULDER	25.4
STA. 143+46.19 TO 144+00.00, RT.	18.0
TOTAL =	56.0

50105220 PIPE CULVERT REMOVAL

LOCATION	QUANTITY (FOOT)
STATION	
142+77.9, RT.	40.3
143+36.5, LT.	39.2
TOTAL =	79.5

50901760 PIPE HANDRAIL

LOCATION	QUANTITY (FOOT)
STATION	
On west wings of structure	12
Rt 143+20 On top of retaining wall	45
TOTAL =	57

54200427 PIPE CULVERTS, TYPE 1 RCCP 12"

LOCATION	QUANTITY (FOOT)
STATION	
142+50.00, 24.00 RT. TO 142+97.50, 25.86 RT.	45.9
143+17.00, 26.27, LT. TO 143+57.00, 25.00 LT.	40.0
TOTAL =	85.9

54213657 END SECTIONS 12"

LOCATION	QUANTITY (EACH)
STATION	
STA. 142+50.0, 24.0', RT.	1
STA. 143+57.0, 25.0', LT.	1
TOTAL =	2

60100945 PIPE DRAINS 12"

LOCATION	QUANTITY (FOOT)
STATION	
STA. 142+94.65, LT.	9.5
STA. 143+20.69, RT.	11.5
TOTAL =	21.0

60602800 CONCRETE GUTTER, TYPE B

LOCATION	QUANTITY (FOOT)
STATION	
143+70.19 TO 144+00	29.9
TOTAL =	29.9

60603200 CONCRETE GUTTER TRANSITION (SPECIAL)

LOCATION	QUANTITY (FOOT)
STATION	
STA. 143+46.19 TO 143+70.19	24.0
TOTAL =	24.0

60900240 TYPE C INLET BOX, STANDARD 609006

LOCATION	QUANTITY (EACH)
STATION	
STA. 142+94.65, LT.	1
STA. 143+20.69, RT.	1
TOTAL =	2

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

LOCATION	QUANTITY (EACH)
STATION	
STA. 140+50, RT.	1
STA. 140+75, LT.	
STA. 145+45, RT.	
STA. 145+70, LT.	

70106700 TEMPORARY RUMBLE STRIP

LOCATION	QUANTITY (EACH)
STATION	
NORTH PROJECT LIMIT	3
SOUTH PROJECT LIMIT	3
TOTAL =	6

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

LOCATION	QUANTITY (FOOT)
STATION	
STA. 140+00, RT. - STOP BAR, 24"	72.0
STA. 141+74.5 TO 144+38, (STAGE I)	527.0
STA. 141+74.5 TO 144+44, (STAGE II)	539.0
STA. 146+20, LT. - STOP BAR, 24"	72.0
TOTAL =	1210.0

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ. FT.)
STATION	
STA. 141+74.5 TO 144+38, (STAGE I)	175.7
STA. 141+74.5 TO 144+44, (STAGE II)	179.7
STOP BARS	
JOB SITE	48.0
TOTAL =	403.4

70400100 TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STATION	
STA. 141+74.5 TO 144+38 (STAGE I)	269.5
TOTAL =	269.5

REVISIONS	
NAME	DATE
dml	7/24/06
handrail adj.	
temp barr adj.	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: MARCH, 2006

DRAWN BY: JH
CHECKED BY: FML