

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	QUANTITY (FOOT)
STATION	
STA. 141+74.5 TO 144+44 (STAGE II)	269.5
TOTAL =	269.5

72400500 - RELOCATE SIGN PANEL ASSEMBLY - TYPE A

LOCATION	QUANTITY (EACH)
STOP SIGN - STA. 142+92, RT. TO 143+95, 23.3' RT.	1
SLOW - CHILDREN AT PLAY - STA. 142+92, RT. TO 143+95, 23.3' RT.	1
STOP SIGN - STA. 143+21, LT. TO 143+20, 25.0' LT.	1
RR CROSSING - STA. 143+62, LT. TO 143+65, 18.0' LT.	1
TOTAL =	4

**70300220 TEMPORARY PAVEMENT MARKING - LINE 4"
78005110 EPOXY PAVEMENT MARKING - LINE 4"**

LOCATION	QUANTITY (FOOT)
STATION	
STA. 142+02.50 TO 144+10.00, CENTER LINE DOUBLE SOLID YELLOW	415.0
STA. 142+02.50 TO 142+37.71, RT. EDGE LINE SOLID WHITE	35.2
STA. 142+98.46 TO 144+10.00, RT. EDGE LINE SOLID WHITE	111.4
STA. 142+02.50 TO 143+16.19, LT. EDGE LINE SOLID WHITE	115.0
STA. 143+74.52 TO 144+10.00, LT. EDGE LINE SOLID WHITE	35.5
TOTAL =	712.1

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
JOB SITE	2
TOTAL =	2

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	QUANTITY (EACH)
JOB SITE	2
TOTAL =	2

REVISIONS	
NAME	DATE
DML	8/15/07
Removed rpms	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: MARCH, 2006

DRAWN BY: JH
CHECKED BY: FML